# CONCRETE

## CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

**JULY 1961** 



VOL. LVI. NO. 7

FIFTY-SIXTH YEAR OF PUBLICATION

PRICE 2.

AMNUAL SUBSCRIPTION 24s. POST FREE: \$3.90 in Canada and U.S.A.

#### LEADING CONTENTS

Structural Safety								235
Book Reviews .								238
Balcony Slabs Spannin	ng in	Tw	o Die	ectio	ms			
By L. S. Müller								239
London Telecommuni	catio	ns C	entr	•				245
A Practical Comprehe Reinforced Co						ning		
By J. Rygol, B.Sc.(En	g.)							247
Developments in the	Read	ly-m	ixed	Conc	rete	Indu	stry	255
Failures of Foundation	ns							261
Vehicles for Ready-mi	ixed	Con	crete			44	0 1	263

-

ISSUED MONTHLY

Registered for Corndian Magazine Post

**BOOKS ON CONCRETE** 

For Catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.I.

#### INDEX OF ADVERTISERS

4.00 4.0	Page		high
A.B. Mould & Construction Co. Ltd	. Ivili	LECA (GREAT BRITAIN) LTD.	
A.C.E. MACHINERY LTD	. xxxii		xxii lvili
ALLAM E. P. & Co. Lyn.	Ixxvii	LEVERTON (IND. "IAL) LTD.	-
ALLIED BUILDING CONMODITIES	. alvi	LILLINGTON, GED. & & Co. LTD.	bri
ANGLIAN BUILDING PRODUCTS LTD	, Ini	LIND, PRINK, & Co. LID	Risi
ATLAS STORE CO. LTD.		LONGDEN, GRONGE, & SOW LID	KRIK
BARVIS, A. & C., LTD		MASSER, A. H., LTD	Ixx
Berry's Engineering Co	. xvi	Masser, A. H., Ltd	yix
BOULDER EQUIPMENT LTD. BOYER, Wm., & SONS LTD. BRATTHWATTE & CO., EMBINEERS LTD. B.R.C. ENGINEERING CO. LTD.		MCCALLS MACALLOY LTD	XIX
BOYER, WM., & SONS LTD	. laiv	Machinery (Continental) Ltd	HVE
RRC ENGINEERS CO. LED.	nin, neiv	MANORITE LEG.	
BRETT, ROSERT, & Sous LTD	. zviii	MAY & BUTCHER LTD	xvili
BRITISH ONYGEN CO. LTD			luvi
BRITISH STERL PILING CO. LTD		MILLARS' MACHINERY CO. LTD IN.	AXIII
BUILDING & CONSTRUCTION CO. LTD	- Samuelan	MILLS SCAPFOLD CO. LTD	-
BYRD, A. A., & Co. LTD	. luxix		NXIV
CALEDONIAN MECHANICAL HANDLING CO. LTD.	Innail	MULCASTER, WM., & Co. (CONTRACTORS) LTD 2	exisi Livisi
CALEDONIAN MECHANICAL HANDLING CO. LTD.		Myras, Faro, Lyp.	
CAPLIN ENGINEERING Co. Lyp.	. zcii	OMNIA CONSTRUCTIONS LTD.	
CASTLEHILL SAND & GRAVEL CO. LTD	EXEVIII		
CEMENT & STEEL LTD	, zii	P.S.C. Equipment Ltd zevi, 1	EAST
CHRETHAM, ALEX. I., LTD	BRRIV	P.Z. PRESTRESSING CO. LTD.	VII
CHEETHAM, ALEX. J., LTD	. lanii	PASHLEY & TRICKETT LTD	AAA
COMEN, GRORGE, SONS & CO. LTD		PORTASHLO LTD	aviii
COMEN, GRORGE, SONS & CO. LTD	maniii	POWELL DUPYRYST TIMBER INDUSTRIES LTD	-
COLUMN LED		PRESTRESSED SALES LTD	-
CONCRETE PILING LTD.	. KERV	PRIEST, B., & SONS LTD.	- 1
CONCRETE PROOFING CO. LTD	. unii	PUMPERAT HIRA CO. LTD.	ivii
CONCRETE PUMP CO. LYD	, xlii	RANALAN STEEL MOULDS LTD	zliv
CONEYBEARE & Co. LTD	ERVIII	READY MIXED CONCRETE LTD	zliz
CONTAIN CONCRETE CO. LTD		ROVER CAR CO. LTD	-
COWLIN, WM., & SON LTD	. zvil	RUSAR & TOMPKINS LTD	lv.
CROYDON REINFORCED FIRMEGEASS CO	. ziv	RYLANDS DRUTHERS LID	100
D.A. MODELS LTD	. xlvii		lxix
DANDRIDGE, J. & A., LTD		SWARP JONES & Co. Ltd	-
Da lous	liv		xxvi
DE JOHO	. ali	SIMPLEX CONCRETE PILES LTD	Ixii
DORMAN LONG & CO. LTD.	. lx	SOMERSET WIRE CO. LTD	INAV
DOUGLAS, ROBERT M. (CONTRACTORS) LTD	-	STELMO LTD.	LERE
DICREMS, STUART B., LTD. DORMAN LONG & CO. LTD. DOUGLAS, ROBERT M. (CONTRACTORS) LTD. DURATURE & WIFE LTD.	. luv	STEHT PRECAST CONCRETE LTD	lxiv
EMPIRE STONE CO. LTD			xxiv
ENGINEERING DESIGN & CONSTRUCTION LTD.	. Ini		xciii
EXPANDITE LTD	REEN	STORER, WM. T., & CO. LTD	iv xxiv
FARR, A. E., LYD.	- xxiii	STUART'S GRANOLITHIC CO. LTD	la
FLERIBLE DRIVE & TOOL CO. LTD	xxviii	Sussex & Dorking Bruck Cos. Ltd	-
FORD MOTOR Co. Lyd.	. axi	TARMAC LTD	
FRANKIPILE LTD.	. 111	TECHNICAL PAINT SERVICES	400
G.K.N. REIMPORCEMENTS LTD	. lxii	TENTOR BAR Co. LTD.	-
GLEESON, M. J. (CONTRACTURE) LTD		Trusquis Lyp.	xix
GOODES ENGINEERING LTD	. =	THAMES PLYWOOD MANUFACTURERS LTD	Mi
GUNITE CONSTRUCTION Co. LTD	. zivi	TILEMAN & Co. LTD.	-
HALL & CO. LTD	. vi	T.P. POLYPLASTIC CONVERTERS LTD	alvi
HENSMALL, JOHN, LTD. HILTON GRAVEL LTD.	. XV	TRENT GRAVELS LTD	MIN
HILTON GRAVEL LTD	. laxi	TRITON ENGINEERING Co. (Sales) Ltd. TRUCK-MEX (MIDLANDS) LTD.	aliii
PROLETERS FILES 1 FD		TUNNEL PORTLAND CEMENT CO. LTD IN	ERV
HOLST & CO. LTD. HOWARD, C. A. E. C., LTD.	HEV	Unistrut Division of Sanery-Sheldon Ltd.	-
HUNTLEY & SPARKS LTD.			
		VOLKMANN, O. A.	lais
IDEAL CASEMENTS (READING) LTD	beer	WALKER WRIGHT & Co. LTD	1
PAPERIOL CREMICAL INDUSTRIES LID	DAKE	WELBECH TRADING CO. LID	-
JOHNSON, RICHARD, & NEPHEW LTD	. lavii	Wellerman Bros. Ltd.	XXX
JOHES, T. C., & Co. LTD		WESTWOOD, JOSEPH, & CO. LTD	vii
KERNER-GREENWOOD & Co. LTD.	. **	WHITECROSS WIRE CO. LTD.	-
King, J. A., & Co. Ltp.	XXXIV	WHITEHEAD IRON & STEEL CO. LYD	E, E
		WHITLEY MORAN & CO. LTD	luii
LAPARGE ALUMINOUS CRIMENT Co. LTD.	- lxxxi	WOLF ELECTRIC TOOLS LTD.	LM13
LAWLER AYERS & CO. LTD			-
LAWS & SON (STAINES) LTD		YOURSHIRE HERRESIGUE CONTRACTING CO. LTD	is




### facts

THE CO-OPERATIVE BANK AND OFFICE BUILDING ON THE MARINA LAGOS · NIGERIA

#### STRATA

Three penetration tests were taken with the Dutch Penetrometer, of which No. 2 is reproduced below. It will be observed that this shows a pressure of 80 kgs per square cm at a depth of 30 feet, at which level the piles were based.





#### PROBLEM

A firm foundation for an important new building was required on the attractive Marina at Lagos. The ground at levels where ordinary foundations would normally be made was of strength inadequate for the loadings. Moreover, the ground water level was within a few feet of the surface.

#### SOLUTION

Trial penetration tests with the full size machine were taken, and these provided general confirmation of the penetrometer findings, and showed that piles could be formed satisfactorily at the economic depth of 31 feet to carry working loads of 50 tons.

Contract No.: BWA/L.3 . Client: The Co-operative Bank Limited Location: Lagos · Nigeria, on the Marina · Architects: Messrs. Fry, Drew, Drake & Lasdun Engineers: Messrs. Ove Arup & Partners · General Contractors: Cappa & d' Alberto Ltd. Type of Structure: Eight-storey Bank & Office Building - Number & Type of Piles: 66 Franki Driven piles Working Load: 50 tons · Average Length: 31' 0"



FRANKI At your Service throughout the World

FRANKIPILE LIMITED - 39 VICTORIA STREET - LONDON S.W.I - TELEPHONE: ABBEY 6006/9

#### INDEX OF ADVERTISERS

	Page		1
A.B. Moura & Construction Co. Lim.	. IVIE	LECA (GREAT BRITAIN) LTD.	-
A.C.E. MACHINERY LOD.	, seed	LENDS ON & GREAGE CO. LTD	220
ARLIAN, R. P., & Co. LTD.	- Europi	Luminos (Incomes as)	ziviii
ALLAN, E. F., & CO. LIB.	, xlei	Leverson (Indonesia) Link	Ivi
ALLIED BUILDING COMMODITIES	144	Lien Peres & Co. Lun	- 1
ATLAS BROWN CO. LTD.		Landacin Iro. Lavarron (Internation) Len. Litanogroup, Galence, & Co. Lin. Line, Parsa, & Co. Lin. Longour, Gonoma, & Son Lin. Longour, Gonoma, & Son Lin.	XXII
BARYS ENGINEERING CO	40 0 22	MAGNED, A. H., LTD	laz
DEARY'S ENGINEERING CO.	zvi	MCCALL & CA. (MREPPERLE) LTD	xiv
Borra, Wa, & Loss Ltp.	hiv		BEREE
Buckey William Committee Ton	· · · · · ·	Macontonia (Company of 1 and	1177
BRACTHWATTE & CO., CHOUNERS LTD B.R.C. ENGARGEROND CO. LTD BRATT ROBERT, & SONG LTD	humbs, noiv	MAGNITE LID.  MAY & BUNGINE LID.  MILANS FLOOR LID.  MILANS MAGNINAY CO. LID.  MILANS MAGNINAY CO. LID.	-
Burry Rosery & Sons Lyn	avill .	May & Buscaye Lyn.	lavil
Surma Ogrosa Co. Lrp.		MILMANN FLOORS LTD.	Exvi
Buston STERR PRING Co. Erp.		MILLARD' MACHINERY CO. LTD	Exvi
Busines Orrean Co. Lto. Beathes Street Filips Co. Etc. Business & Cossensioness Co. Lto. Brad, A. A., & Co. Lto.		MILLS SCAPPOLD CO. LTD	-
Byan, A. A., & Co. Lyn	innin	MODELLAR CONCRETE CO. LEO	REZIV
Casus Course Lto	. lexxii	Mona, A., & Co. Lep	ixxiii
CALEDONIAN MECHANICAL HARBLESO CO. LT		MULCASTER, WM., & Co. (Coursacessas) Len	RIVIN
CARLIN ENGINEERING CO. LTD.	ncii	Myens, Fran, Lyn.	
CASHARILI SHID & GRAFEL CO. LTD.		ONDIA CONSTRUCTIONS LTD	
CREATE MARKETING CO. LTD.	. REEVILL		REVI
COMBINE & SOURCE LTD.  CHRISTIAN & STREEL LTD.  CHRISTIAN & STREEL LTD.  CHRISTIAN & STREEL LTD.  CHRISTIAN & SOURCE PRODUCTS LTD.  CHRISTIAN & NAMERIAN LTD.  COMBINE, GROOME, SOUR & Ch. LTD.	e . 185	P.S.C. EQUIPMENT LYB. REVI. P.Z. PRESTRESSING CO. LYD. PARLEY & THERRY LYD.	WHAS
CHRETNAM, ALEX. J., Lvn.	, RELIV	Princer & Topograph Lon.	233
CHARGOLD BUILDING PRODUCTS LTG	. laxii	PITMAN, SIR ISAAC, & Sous Led	All Parks
CARLETTARI & NIBLATE LTD.		PORTANDO LTD.	hrviil
CONCRETE LTD.	. axxiii	POWELL DUPPNYS TIMBER INDUSTRIES LTD	
Contractor Line	. ARRY	PRESCRIPTION SALES LID	-
CONVERSE LTD.		PRESCRIMED SALER LTD	STATE OF THE PARTY.
Concern Property Co. Lto.	. xxii	PUMPERET HIME CO. LTD	Ivi
CONCRETE PILIPO LTD. CONCRETE PILIPO LTD. CONCRETE PILIPO LTD. CONCRETE PILIPO LTD. CONCRETE POUP CO. LTD. CONCRETE CONCRETE CO. LTD. CONCRETE CONCRETE CO. LTD. CONCRETE WAS, & SOR LTD. CROYDON REINFORCED FIREEGLASS CO.	. zin	RABARAM STREE MOULDS LED	zliv
CONFEDERNE & CO. LTD.	. REVES	READY MINED CONCRETE LID	zhiz
CONTAIN CONCRETE CO. LTD.		ROVER CAR CO. LTD	100
Cowess, WM., & Son Lyp	zvii	Russ di l'oungine Lro.	-
CROYDON REINPORCED FINGEGLASS Co.	ziv	RYLANDS BROTHERS LTD	- Iv
D.A. MODELS LTD.  DANDRIBGE, J. & A., LTD.  DAVIDSONS PAPER SALES LIG.	. sivii	SHALOGRETE PRODUCTS LTD	Inda
DANDSTROE, I. & A. LTD.	A CONTRACTOR	SHARP JONES & CO. LTD. NISHING SONS & COOKE LTD. SOMPLET CONCERT PLAS LTD. SOMPLET WINE CO. LTD. SPERGER WINE CO. LTD. SPERGER WINE CO. LTD.	
DAVIDSONS PAPER SALES LID	1iv	States, Sous & Cooke Lto	IXXV
DAVIDSONS PAPER SALES 1.10. DE JONO. DICTEMA, STUMET B., LTD. DOUBLAS, ROBERT M. (CONTRACTORS) LTD. DOUBLAS, ROBERT M. (CONTRACTORS) LTD. DUBATORS N. WIRE LTD.	Mix	Sources Concern Price Lto	
DICKERS, STUART B., LED		SOMERMET WIME CO. LTD.	lxi
DORMAN LONG & Co. LYD.		Senson Wine Co. Lto.	EXEN
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.		STRING LTD.	luxx
	THE REAL PROPERTY.	SPIRAT PROCESS COFFIRM LTD	Ingis
EMPINE STORE CO. LTD	70	Some Course Savings Co. Line	Reil
ENGINEERING DESIGN & CONSTRUCTION LTD		STORE COURT BALLAST CO. LTD. STORER, WM. I., & Co. LTD.	Ger.
Executive Line.	. ANEVI	STERNISH BY LEVEL COMMERCE LAND.	XX
PARS, A. E., LTD. FLEXIBLE DRIVE & Toge Co. LTD. FORD MOTOR CO. LTD.	nuiti	STURRET'S GRANDLITHIC CO. LID	h
FLERIBLE DRIVE & Tool Co. Ltp.	ALL REVINE	Scarce & Donasso Bance Con Ltd.	
Fone Moron Co. Lro.	3.81	TARMAC LID.	100
Persona Lto.	· · ·	TECHNICAL PAINT SERVICES	-
G.K.N. REINFORCEMENTS LTD	. buil	Tauron Ban Co. Lit.	-
CARRESON, M. J. (CONTRACTORS) LTD.		Terrous Lyn	xis
Guesson, M. J. (Contractors) Ltp	42 mm	THANKS PLYWOOD MANUSACTURES LTD	M
GUARTE CONSTRUCTION CO. LTD	nivi	THEMAN & CO. LYD.	
Hate & Co. Lyn	. W	T.P. POLYPLASTIC CONVENTERS LTD. TRENT GRAVELS LTD. TRICOR ENGINEERING CO. (SALIE) LTD. TRUCK-Mix (Middlessed) LTD.	-
HENDRICH LID.	NA NA	TREST GRAVELS LTO.	. ziv
HILTON GASSEL LTD.	. inni	Trees May (Many sweet I realis) Lyb.	×HI
Picamenana Picame Lyn.		TUNNEL PORTLAND CEMENT CO. LTD.	LEARY.
House & Co. Leo.	XXV		-
HOUST & Co. LTD. HOWARD, C. A. E. C., LTD.	B.	Universit Division of Sankey Sheldon Ltd.	-
PROPERTY & SMARKE LTD	A	VOLENAMM, O. A.	. Inte
PORAL CARRIERS (READONS) LTD.			1000
IMPERIAL CREMICAL INDUSTRIES LTD	. lanev	WALKER WRIGHT & Co. LTO	0 2 1
	Named .	WEERECK TRADING CO. LTS.	-
JOHNSON, RICHARD, & NEPHEW LTD	lavii	Westernan Joseph & Co. Lan.	. EXX
	Bertall Bay	Westerness Wise Co. Lan.	48
KENNER-GREENWOOD & Co. LTD.	32	Wellings Broke Lite. Wastwood, Joseph Co. Lite. Whittocaus Wire Co. Lite. Westween Wire Co. Lite. Westween Mona & Syren Co. Lite. Westween Mona & Co. Lite.	
Kino, J. A., & Co. Lro	. ERRIV	WHITTERY MORAN & Co. LTD.	C 2
	. lassi	Personal Lines	ball
LAWARDE ALUMINOUS CREEKE CO. LED. LAWARD AVERS & CO. LTD. LAWS & SON (SYCLES) LTD.	-	WOLF ELECTRIC TOOLS LYD	
Laws & Son (System) Lyp.		Y-MERITE BERNEROUN CONTRACTING CO. LTD.	11-6
COURSE DESCRIPTION OF THE PARTY		Comment or the second of the last of the l	F-11-P-



## facts

THE CO-OPERATIVE BANK AND OFFICE BUILDING ON THE MARINA LAGOS · NIGERIA

Three penetration tests were taken with the Dutch Penetrometer, of which No. 2 is reproduced below. It will be observed that this shows a pressure of 80 kgs per square cm at a depth of 30 feet, at which level the piles were based.





#### PROBLEM

A firm foundation for an important new building was required on the attractive Marina at Lagos. The ground at levels where ordinary foundations would normally be made was of strength inadequate for the loadings. Moreover, the ground water level was within a few feet of the surface.

#### SOLUTION

Trial penetration tests with the full size machine were taken, and these provided general con-firmation of the penetrometer findings, and showed that piles could be formed satisfactorily at the economic depth of 31 feet to carry working loads of 50 tons.

Contract No.: BWA/L.3 · Client: The Co-operative Bank Limited Location: Lagos · Nigeria, on the Marina · Architects: Mesars. Fry, Drew, Drake & Lasdun Engineers: Messrs. Ove Arup & Partners · General Contractors: Cappa & d' Alberto Ltd.

Type of Structure: Eight-storey Bank & Office Building · Number & Type of Piles: 66 Franki Driven piles. Working Load: 50 tons . Average Longth: 31' 0"



FRANKI At your Service throughout the World

FRANKIPILE LIMITED - 39 VICTORIA STREET - LONDON S.W.I - TELEPHONE: ABBEY 6006/9

#### STORER'S



Sawing, Planing and Houlding Hills and Storage Yards at Barking

# for SOFTWOOD

Wm. T. STORER & CO. LTD.

Timber Importers and Merchants

ESTABLISHED 1913

Telephone: RIPpleway 0301 (10 lines)

RIVER ROAD - BARKING - ESSEX



#### CONSTRUCTED OF EMPIRE STONE

This imposing staircase, constructed of Empire Stone at the Crystal Palace, London, in 1911, still stands today after fifty years' continuous use. Through these years millions of visitors to this famous site have used it, and today it proves yet again the excellence and durability of Empire Stone under the most exacting conditions.

IN 1911
AND STILL
IN USE
TODAY



The illustration above shows Their Late Majesties King George V and Queen Mary descending the staircase at the opening of the Festival of Empire at Crystal Palace, 1911.

#### EMPIRE STONE CO LTD

THANET HOUSE 231 STRAND LONDON WC2

BERKELEY HOUSE, BIRMINGHAM 16 NARBOROUGH NR. LEICESTER 26 GREEK STREET STOCKPORT

#### BRITAIN'S LEADING BUILDERS' MERCHANTS

We produce and distribute-

# CONCRETE AGGREGATES READY-MIXED CONCRETE SAND-LIME MORTAR

HALL & CO.

LIMITED

Head Office: VICTORIA WHARF · CROYDON · Tel: 4444
London Office: CHANTREY HSE, ECCLESTON ST, SWI · Tel: SLO 7122

-and now we introduce



LIGHT-WEIGHT
GAS-CONCRETE UNITS

The Building Material of the Future available shortly-write to us for details

A HUNDRED BRANCHES IN ENGLAND & WALES



#### the modern method of



# PRESTRESSED CONCRETE DESIGN AND CONSTRUCTION



This system is described and illustrated in our Catalogue, together with some of the many important contracts on which it has been used. Engineers and Contractors interested in the latest developments should send for a copy.

#### THE PZ PRESTRESSING CO. LTD.

BURCOTT LODGE, BURCOTT, WING, LEIGHTON BUZZARD.


TELEPHONE - WING 286

# wESTW00Ds

#### HI-LOAD BRIDGE BEARING

TAKES 600 TON LOAD

4" DIA. ROLLER, 24"



Rolling parts made from steel to a special specification. Precision workmanship. A very compact roller bearing for heavy reaction. Completely enclosed in grease box. No maintenance required. Bearings designed to suit all loads and conditions.

Apply for further details:

**IOSEPH** WESTWOOD & CO NAPIER YARD MILLWALL LONDON

Phone: EASt 1043 Cables: Westwood London

Grams: Westwood Easphone London



Reconstruction of Whitehills Harbour

by

THE

#### YORKSHIRE

# HENNEBIQUE

Contracting Company Limited


Established 1904

CIVIL ENGINEERING CONTRACTORS

HENNEBIQUE HOUSE
YORK

Telephone: York 54656 (4 lines)

CONCRETE AND CONSTRUCTIONAL ENGINEERING JULY, 1961.



# have been regularly used by leading Contractors for reinforced concrete work

since 1903

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL has been used include some of the largest and most important in the country.

We can supply mild steel with an ultimate tensile stress of 28/33 tons to the square inch, medium tensile 33/38 tons to the square inch, and high tensile 37/43 tons per square inch.


We can also supply high tensile bars 40/45 tons to the square inch with a minimum yield of 60,000 pounds per square inch.

# WHITEHEAD IRON & STEEL C? LTON NEWPORT ... THE NAME AND ADDRESS OF THE PARTY OF THE

LONDON OFFICE: Steel House, Tothill Street, S.W.I. Telephone: Whitehall 2984/5. BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412/3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 1603/4. GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.

for bars from 4 to 2 dia.



#### **BAR-BENDING**

with accuracy-speed-economy



ARD-50 MODEL

ELECTRIC OR ENGINE DRIVEN

The ARD-50 Model, illustrated above, has an automatic control which permits the desired bending angle to be pre-set, greatly facilitating repetition bending. The bottom illustration shows the bending of an angle loop in one operation. This model is also fitted with a backrest for multiple bending of small diameter bars. We also supply, at extra cost, a special device for bending Hoops and Spirals, and formers and backrests for special steel such as "Square Grip," "Twisteel," and "Tentor," etc. This model is complete with standard accessories for bends on a 4D basis, and can be fitted with Electric motor, Air-cooled Petrol engine or Air- or Water-cooled Diesel engine. Our range of bending equipment also includes the RAS-40 model for bending bars up to 1½ in. diameter. Both models are available for sale or hire. Full details will be sent on request.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT.

Telephone: Chatham 45580.

Telegrams & Cables: Cembelgi, Chatham.

## DRILLED FOUNDATIONS



Architects Consulting Engineers Mails Contractor

ir falm Burnes, Fait and Persners he Arap and Partners

A modern office block which is being erected on our drilled foundations at Vauxhall Bridge Rd London for Chesterfield Properties Limited

We have modern mobile plants which can drill foundations of various diameters up to depths of 100 feet or more. Tel: Abbey 7361 or send your enquiries to

#### PETER LIND

Peter Lind and Company Limited Romney House Tufton Street London SWI

#### DID YOU KNOW ???

# FIBREGLASS MOULDS FOR PRECAST CONCRETE

GIVE YOU -

- \* NO STRIPPING (NORMALLY)
- \* FAR SUPERIOR FINISH
- \* EXTREME FREEDOM IN DESIGN
- \* WONDERFUL HANDLING LIGHTNESS
- \* MUCH QUICKER PRODUCTION
- \* STEEL-LIKE TOUGHNESS
- \* INCREASED MOULD LIFE

ALL FOR - NO EXTRA COST!
WHY DELAY!

Send copy of your quote to (or ask our Technical Representative to call)—



DON REINFORCED FIBREGLASS CO

NDON ROAD CROYDON SURREY TEL: CROYDON 4699

MANY STANDARD MOULDS IN STOCK

# READICRETE

THE MODERN READY MIXED CONCRETE PLANT WE HAVE RECENTLY OPENED AT CHESTER, TOGETHER WITH THAT AT HALKYN, ENABLES US TO SUPPLY QUALITY CONTROLLED READY MIXED CONCRETE THROUGHOUT NORTH WALES AND CHESHIRE TO ANY SPECIFICATION OR STRENGTH.

#### JOHN HENSHALL (Quarries) Ltd

Tel: Halkyn 353

30 JAMES ST, LIVERPOOL, 2

Tel: Central 6070

SEALAND INDUSTRIAL ESTATE, CHESTER

Tel: Chester 24192

# READY MIXED CONCRETE

OF THE FINEST

QUALITY


IS ALWAYS

AVAILABLE

FROM UP-TO-DATE

PLANTS

IN THE AREA SHOWN HERE



# INSEPARABLE from REINFORGEMENT



. . . OF COURSE!

the specified concrete cover is accurately maintained . . .

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vise-like grip in the desired position on all types of reinforcement, including meeh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem.

#### CONSULT

#### THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conflictions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.
Registered Nos. 870,560, 886,239. English and foreign patents pending.



#### **B.E.C. BEARER BLOCK**

FOR GROUND BEAMS · BARREL ROOFING BRIDGES · MAT WORK · ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

Enhance your Prestige. Specify and use with confidence. BERRY'S ENGINEERING CO.

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-2 CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

#### CAR PARK CONSTRUCTION NFORCED CONCRETE



Consultant Architect: R. Jelinek-Karl, Esq.
Joint Consulting Engineers: Messes, E. N. Underwood and G. C. Mander & Partners.

The structure of this recently completed multi-storey car park at Bristol was erected by us in 5 months. There is over \frac{1}{2} mile of eontinuous ramp in this reinforced concrete building, able to accommodate 550 cars. Our leadership in this type of construction, and unrivalled experience and knowledge of reinforced concrete, combine to give a construction service capable of handling any contract with utmost efficiency.

THE PIONEERS OF REINFORCED CONCRETE CONSTRUCTION IN THE WEST OF ENGLAND

WILLIAM

COWLIN

AND SON LTD

Head Office STRATTON STREET . BRISTOL 2

Telephone: 22132 (7 lines) Telegrams: Construct Bristol

South Wales Office

PENARTH ROAD . CARDIFF

Telephone: 32736 (2 lines)

# exposed aggregate panels are more attractive with

the colour "dry-dash" which is interesting and everlasting

# DURITE

used throughout the British Isles

PRODUCED BY

# BRETT'S

DURITE is an economical material which provides Architects and Engineers with an opportunity of specifying a highly attractive exposed-aggregate surface finish for precast and insitu concrete for contracts in any part of the British Isles. Free samples are readily available on request.

WE ARE ALSO PRODUCERS OF CONCRETE AGGREGATES AND READY-MIXED CONCRETE IN



DELIVERING: Canterbury, Sheerness, Margate, Ramagate, Herne Bay, Ashford, Charing, Lydd, Dover, Faversham, Sittingbourne, Whitestable, and district.

Details and samples are available on request,

ROBERT BRETT & SONS LTD.

ST. LAWRENCE HOUSE NEW DOVER ROAD, CANTERBURY. TELEPHONE: 3211

#### FLEET BUILDING · LONDON



ANOTHER PROJECT COMPLETED BY

TERSONS

LONDON . BIRMINGHAM . EDINBURGH . CARDIFF

PUDLO' PROVIDES PROOF . . . No. 3 OF A SERIES

#### Underground story...

#### of Waterproofed Ready-Mixed Concrete

When, in 1958, the beer cellar of the 'Harp' public house at Parson's Mead, Croydon, was excavated for rebuilding, water was found to be present at a depth of only 3 ft. 6 in. below the level of the upper surface of the old floor. To combat these inherently damp conditions 'Pudlo' CEMENT WATERPROOFING POWDER was specified for the READY-MIXED

CONCRETE used in the new floor.

\*Pudlo Waterproofer was also used in the internal rendering of the outer walls and, to ensure complete protection from damp penetration, a 'Pudloed' cove was formed at the junction of the wall and floor.

#### TECHNICALITIES:

approximately 1,250 square feet. Floor

Waterproof Ready-Mixed concrete to 8" thick, with granolithic

auritice.


Alig: 4:2:1 reinforced with No. 8 S.R.C. fabric and waterproofed with 16 b. "Public" cement waterproofer per cubic yard of "SURECRETE" Ready-Hixed Concrete.

Walls Hard semi-engineering brick, to a thickness of 13t inches.

#### Internal Rendering

Two parts Westerham Send. One part Portland Cement. 5 lb. 'Pudio' to every 100 lb. cement, spelied in three coats to a minimum thickness of one inch.

Beer Cellar of the " HARP," Parson's Mead, Croydon. By courtesy of Page and Overton's Brewery Ltd.



Archisacts: Leonard Chignall & Se F.I.A.A., M.INST.R.A., M.R.SAN.I., Romford.

Contractors: Galbraith Bros., Craylord.

Sole Proprietors and Manufacturers:

Repellent, Plaster Bonder, Frost Protector/Rapid Hardaner, Concrete Plasticiser, Mortar Plasticiser, Coment Hardener/Dust Proofer, Permanent Colours for Coment, 'Fousol' Fire Coment. KING'S LYNN,

other 'PUDLO' products include: Waterproof Coment Paints, Cament Paint Primer, Cament Bonder, External Water

KERNER-GREENWOOD & CO. LTD.,

Telephone: King's Lynn 2293

NORFOLK

#### AN **EXPORT MANAGER'S BEST FRIEND** IS A FORD ENGINE

All over the world the name Ford stands for tough, economical, reliable engines built to the highest engineering standards. That's a big sales-point! All over the world there's the close-knit chain of the Ford Service organisation, with factorytrained engineers backed by stocks of genuine Ford parts. That's an even bigger sales-point!

The Company whose industrial equipment is powered by a Ford engine is a jump ahead of its competitors in world markets. Ford-powered equipment is easier to sell in the first place-and its long life and low running and maintenance costs make it easier to get repeat orders.

Ford Industrial engines range from 15 b.h.p to 100 b.h.p-Diesel or Petrol, 4-cylinder or 6-cylinder. Send the coupon below for full technical specifications.





Please send me full details and dimensions of Ford Industrial engines. Diesel/Petrol Power range required YOUR FIRM'S NAME. For the attention of Mr. ADDRESS

CONCRETE Co. LTD.

116 Richmond Road, Kingston-upon-Thames, Surrey. KINGSTON 7863 and 9252

And 10 Royal Crescent, Glasgow, C.3. GLASGOW DOUGLAS MITI



#### YOUR FAITH TESTED BRAND

THIS LABEL ON CARRIES WITH IT FIFTY YEARS' EXPERIENCE OF MANUFACTURE.

NONE OTHER IS "JUST AS GOOD"

LEEDS OIL & GREASE CO.

ne 22480

LEEDS, 10 'Grams: "Grease, Leeds 10"

#### A. E. FARR LTD.

Specialists in
Reinforced Concrete
Construction
for over
half a century

Head Office: WESTBURY, WILTS.

# AT LAST—A PORTABLE STRESSING BED

#### AT A SENSIBLE PRICE



- IT WILL MAKE-
- . FLOOR BEAMS
- LINTELS
- . PLANK UNITS
- FENCE POSTS
- RAFTERS
- · PURLINS
- . BEAMS



- YOU CAN-
- MOVE IT
- · VIBRATE IT
- STACK IT FOR CURING (STEAM OR NATURAL)
- USE IT IN FACTORY OR ON
- USE IT FOR INSTRUCTION OR RESEARCH

#### PRICE:

COMPLETE BED LESS JACKING

COMPLETE JACKING SET

£225.0.0

(WILL STRESS ANY NUMBER OF BEDS) Comprising: 2 Hydraulic Rams, 2 Pumps, 2 Pressure Gauges with Flexible Hoses and Oulck-Couplers

#### Specification:

Construction—All Steel
Capacity—50 tons Max.
For use with—Wire or Strand
Making Area

Overall Size

33 ft. × 4 ft.
Weight

2,400 lb.

#### STRESSING DEVELOPMENTS LTD.

95 KINGSTON HILL, KINGSTON-L'PON-THAMES 'PHONE: KINGSTON 2372 'GRAMS: STRESS, KINGSTON


AND
CONSTRUCTION
OF
REINFORCED
CONCRETE
FRAMEWORKS

HOLST

Civil Engineering Contractors, Reinforced Concret

46 CLARENDON ROAD . WATFORD

#### HYDRADUCT SHEATH



HYDRARIGID

HYDRARIGID

**HYDRAFLEX** 

Hydraduct is an extremely robust form of sheathing for prestressing tendons and meets the most stringent requirements of Designers and Contractors; problems which may be encountered in transportation and site handling have been carefully considered.

#### **PSC GROUT INJECTION EQUIPMENT**



P.S.C. hand-overated disphragm, direct displacement grout pump with electrically operated stirrer.



P.S.C. power-operated grout injection pump.

The subject of cable grouting is one that P.S.C. Equipment Limited have studied intensively and for which a range of equipment has been developed.

#### PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

P.S.C. Equipment Limited, members of the Freyssinet International Organisation, have available a range of prestressing systems including Freyssinet MultiWire, Freyssinet MultiStrand—FreyssiStrand, P.S.C. MonoWire, P.S.C. MonoStrand and P.S.C. Pretensioning. Full details and complete technical information are always available on request.

#### REYSSINET RUBBER BRIDGE-BEARINGS



. . . the modern method of supporting bridges and other civil engineering structures. They are more economical and technically superior to traditional steel bearings and are widely recommended. Freyssinet bearing pads are of unit bonded construction. The design of the pads is based on the relationship between loads, displacements and rotations, and, as no moulding is required, each case is treated as unique and the proposed pad calculated accordingly. The highly satisfactory behaviour of this type of pad has been proved by tests and by observation on over 500 bridges on which they have been used. Technical questionnaire forms are available on request.

## FREYSSINET FLAT JACKS



Ref.	Outside Diameter (inches)	Maximum Force (tons) at 2,000 lb./in. <sup>2</sup>
67	2-75	3
12	4-72	9
15	5-90	17
22	8-64	41
25	9-84	54
27	10-6	64
30	11-8	81
35	13-8	114
42	16-5	168
48	19-7	245
60	23-6	337
87	34-2	777
92	36-2	066

These hydraulic jacks of unusual and unconventional design permit enormous forces to be exerted where the movement required is small. They have considerable application in underpinning, levelling, and thrust control in engineering





HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, HIDDX Telephone: Unbridge 35241



#### Moulds and formwork

#### for the concrete industry

A service to the industry ranging from the small equipment illustrated to complete spinning plants, backed by years of technical experience.

We are now operating from our extensive new premises at the address below.

Further details and quotations sent on request

#### Coneybeare

THE ORIGINAL PIPE MOULDS

Coneybeare & Co. Ltd., Torrington Road, Ashford, Kent. Tel: Ashford 1545/6



Model VP 350-A (Swivel Base or Barrow Mounting) Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

For Greater Strength, Firmer Bonding and Better Surfacing of Concrete-

Extra-High Frequency INTERNAL CONCRETE VIBRATORS

- The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.
- Petrol or Electric Drive.
   Robustly built throughout and backed by genuine service.
- Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WETRUBBING CONCRETE, GRINDING, DISC SAND-ING, AND DRILLING (up to I 1 " in Concrete, I" in Steel, and 2" in Wood).

\* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world. 30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENsington 3583



# ONGDENS

OF SHEFFIELD

ST. PETERS CLOSE : SHEFFIELD I









#### REINFORCEMENT

#### by Pashley & Trickett

Our Sheffield works is able to deal efficiently with the accurate bending of steel reinforcement for all types of construction work. We deliver clearly identified supplies to your site by our own transport, as and when you require them. Many building contractors, both large and small, are well satisfied with our service. We will deal with your enquiry promptly.



PASHLEY & TRICKETT LTD STOKE STREET, SHEFFIELD 9 TELEPHONE: 41136-7

#### WELLERMAN BROS. LTD.

SHEFFIELD-HYDE-

#### **Civil Engineering Contractors**

#### SPECIALISTS in

- PRESTRESSED CONCRETE
- STEEL and CONCRETE PILING
- REINFORCED CONCRETE
- DEEP FOUNDATIONS, etc.
- BRIDGEWORKS

Underwater Inspections and Underwater
Cutting by Competent Diver
Licensee's for Aerocem Process of Spraying
Grouting and Pointing.

#### WELLERMAN BROS. LTD.

DUN STREET, SHEFFIELD, 3 EDWARD STREET, HYDE, CHESHIRE

Tel. 23238-9 Tel. 2058 TODAY'S MOST ACCURATE, SPEEDY AND ECONOMICAL SYSTEM OF CONCRETE PREP



# 0

- ON THE JOB" AGGREGATE STOCKPILLI CONTINUOUS HANDSCRAPER FEEDING ... star compartments for 3 to 5 aggreg
  - REMOTE CONTROL OPERATION
    - ... one man operated lever system
      - ACCURATE WEIGHING
- . . . high-angle cement screw/weigher DIRECT REEDING OF CEMENT INTO MIXER PAN
- HIGH-OUTPUT, QUALITY CONCRETE ... rota-forced "Waimer" miner
- ... remotely controlled hopp CONCRETE STORAGE

**TERSONS LIMITED** 

Photograph taken by kind permission of A.C.E. MACHINERY LIMITED PORDEN ROAD BRIXTON LONDON S.W.2

#### THE GAMMON-MORGAN WATER-IN-SAND ESTIMATOR

for the ACCURATE. SIMPLE AND

measuring of the WATER CONTENT IN SAND

The most accurate, simple, and rapid means of measuring the water content in the sand. No weighing or chemicals are required, and an adequate sample is used. The GAMMON-MORGAN WATER-IN-SAND ESTIMATOR should be available alongside every mixer, so that the water content of every mix may be correctly gauged. Full details will be sent on request.

PRICE £3 10s, each (10 Canadian or U.S. dollars). CARRYING CASE (1 15s. (5 Canadian or U.S. dollars).

#### MOISTURE VARIATIONS IN THE SAND

Engineers should specify that the concrete mix shall be adjusted for moisture variation in the sand, so that the total water in the batch shall consist of the water carried in the aggregates plus the water added in the mixer.

COLCRETE

GUN LANE · STROOD · KENT

Phone: Strood 78431/2/3

May we

#### **PRECAST**

#### STRUCTURAL COLUMNS

and

SAVE TIME

SAVE MONEY

J. A. KING & Co., LTD

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENtral 5866 (5 lines)

Telegrams: Kinovique Cent London

# COPPER STR

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unnon-corrolive and is unaffected by wet concrete.
We specialise in the supply
of perforated copper strips
of all required lengths and
widths for expansion joints,
and shell be pleased to
submit prices against detailed specification.

Telephone: FAILsworth 1115/6





OVER

the Forth

REINFORCING BARS

\*UNDER
the Clyde

Colvilles Reinforcing Bars are being used extensively in the Forth Road Bridge project


and in the approaches and portals of the new Ten million pound Clyde Tunnel. For hot-rolled, indented reinforcing bars specify "COLBOND 60" which have a guaranteed minimum yield point of 60,000 lbs. per square inch.



COLVILLES

FITNESS FOR PURPOSE STEELS

COLVILLES LIMITED 196 West George St., Glasgow C.2.





The New Underpass, Hook Road constructed by William Old Limited for the Survey County Council

Expandite Limited produce a complete range of efficient Rubber and PVC Water-stops for every type of joint. Made in various designs and lengths, they are accepted as being the most effective and economical method of ensuring watertight structures.

Expandite Waterstops are specified by architects the world over because, unlike metal waterbars, they are not subject to corrosion and will not fracture with movement.

Not content to rest on their laurels, Expandite are constantly introducing new developments. The HYDROFOIL (PVC) revolutionary design combats all seepage, and is suitable for walls, floors, reservoirs, sewage works, ponds, etc. where limited movement may occur.

If you need advice on any problem concerning Waterstops and their most effective use, the Expandite Technical Service Department is always at your service. Please contact us.



CHASE ROAD, LONDON, N.W.10. Tel: ELGar 4321 (10 lines) Telex 25420 ELGar 1551 (10 lines)

Trafford Park Road, Manchester 17 Telephone: Trafford Park 1285/6
36 Great North Road, Newcastle-upon-Tyne 2 Telephone: Newcastle 23992
Eire: EXPANDITE (IRELAND) LTD., Greenhills Road, Walkinstown, Dublin Telephone: 501512

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD




for

economy in bored foundations

DOWN TO

IIO FEET



A LAING COMPANY

McKINNEY FOUNDATIONS LIMITED
Manor Way, Boreham Wood, Hertfordshire. Tel: Elstree 2854



FERROGRETE was the world's first rapid-hardening Portland Cement. It complies fully with B.S.12: it has normal setting properties and therefore gives ample time for mixing, placing and compacting the concrete. In every form of concrete it gives a higher early strength than ordinary Portland Cement.

See CMC about Cement!


get better than this Blue Circle

cement. I've used them all, see?

Make use of our technical service. For all information please write to:
THE CEMENT MARKETING COMPANY LTD., PORTLAND HOUSE, TOTHILL STREET, LONDON, SW1 - Tel: TATe Gallery 3455
G. & T. EARLE LIMITED, MULL - Telaphone: Nutl 25121

Setting Organisations of The Associated Portland Coment Manufacturers Ltd

#### THE MACALLOY WEDGE ANCHORAGE



The wedge is not intended to replace the threaded anchorage which remains the basis of Macalloy prestressing, but it can at times be a very useful device. This anchorage gives a much greater length tolerance than the threaded anchorages, as the wedge can be sited anywhere on the bar. The device allows bars to be stocked on the site and cut to length and used as required. It can be of great use for instance when it is necessary to shorten piles and in transversely stressing bridge decks where it is sometimes impossible to estimate exactly the finished width. An extra 4" extension adjusts the take-up between the wedge and bar. This anchorage entails the use of only a few fittings all of which are easily set up and detailed. The end anchorage is specially robust and serviceable for a unit of its kind.



#### McCALLS MACALLOY LIMITED

TEMPLEBOROUGH . SHEFFIELD . ENGLAND . P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOAME 0428 . BIRMINGHAM: ACOCKS GREEN 0229 PORTSMOUTH: COSHAM 78702 . MANCHESTER: BLACKFRIARS 1018 WHITLEY MORAN

AND CO. LTD

The North of England

INITE SPECIALISTS

BEHIND EVERY JOB . . . 25 years' experience in the scientific repair of engineering structures



5 OLD HALL ST. LIVERPOOL 3. 'PHONE: CENtral 7975/6 GRANS: Gunite, Uverbool, 3



ABELSON for SKIPS







a pouring skip side










#### How temporary is shuttering? How permanent is formwork?



## modcole that has changed the face of concerns

The new development the face of concrete



Expensive timber formwork, complex moulds, the top-rate joinery necessary to ensure accuracy, are generally major items in costing cast or insitu concrete.

Moldcote is a surface hardener for the internal faces of formwork. It provides a smooth polished surface to the timber which greatly extends its working life.

It also ensures a fine, even face to the concrete which dispenses with the need for lengthy finishing operations.


Advantages of Moldcote

- 1. Improved quality of concrete face.
- 2. Reduced cost of rubbing up and making good.
- 3. Greatly increased life of timber face, which is entirely protected from water or oil penetration.
- 4. The face of the timber remains smooth even after repeated use.
- 5. Highly glazed surface means less release agent is needed.
- 6. Easily applied by spray or brush.
- 7. Will not crack or fiake off.
- 8. No staining of the concrete.

For further details of this brilliant new product which is already being used on numerous important projects, write to:

STUART B. DICKENS LTD.

Manor Way, Boreham Wood, Hertfordshire. Telephone: Elstree 2211



### CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE RESIDVENCE TRACE MARK &



HE CHICKEYS PURP COMPANY LINETER

## THE CONCRETE PUMP COMPANY LAD

Telephone : Western 3546

Telegrams: Pumpcret, Kens, London

for your contracts in the Midlands

## TRUCK MIXED

## CONCRETE

We offer a first-class service in the supply of truck-mixed concrete to all engaged in concrete work in the area shown here. It is always available at short notice to any desired specification, and delivered in any quantity—large or small—to your exact requirements from our

#### THREE PLANTS AT

Tamworth

Atherstone

Atherstone

Atherstone

Atherstone

Atherstone

Atherstone

Himckley

COVENTRY

Bromagrove

Rugby

Leamington Spa

Redditch

Droitwich

Warwick

Southam

Stratford-upon-Avon

Kineton

Oxford Road, Ryton-on-Dunsmore, near Coventry. Telephone: Tollbar 3204 and 3392 Tuttle Hill, Nuneaton. Telephone: Nuneaton 4459 Cock Hill Lane, Rubery, Birmingham. Telephone: Rubery 29

Include our name on your list for future enquiries

#### TRUCK-MIX (MIDLANDS) LTD

OXFORD ROAD

RYTON-ON-DUNSMORE
TELEPHONE: COV. TOLLBAR 3204 and 3392

COVENTRY

# RANALAH for STEEL MOULDS



Phone
BRIGHTON 62216-7-8-9
for IMMEDIATE ACTION

RANALAH STEEL MOULDS LTD LOWER BEVENDEAN · BRIGHTON · SUSSEX

## by McCALLS

BARS . TENTOR . BENDING . MACALLOY . DESIGN

HICALL & CO (SHEFFIELD) LTD.

McCALLS MACALLOY LIMITED

#### TEMPLEBOROUGH · SHEFFIELD · ENGLAND · P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 0428 BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702

MANCHESTER: BLACKFRIARS 1018

WE ARE SPECIALISTS \* LININGS FOR IN THE REPAIR \* SWIMMING AND RECONDITIONING \*

\* WATERTIGHT RESERVOIRS POOLS, ETC.

OF REINFORCED\* LININGS FOR CONCRETE STRUCTURES \*

**TUNNELS** SEWERS \* TANKS, ETC.

CONSTRUCTION WESTERN HOUSE, HITCHIN, HERTS

TELEGRAMS: 'GUNITE. HITCHIN'

TELEPHONE: HITCHIN 4371

An Air-entraining Plasticiser for Mortar

- Eliminates the use of all lime in Sand-Lime-Cement

- mortals.

  Increases plasticity and workability.

  Better adhesion is achieved.

  Reduced possibility of cracking and crazing.

  Helpa to prevent the penetration of frost into the
- Recommended for brickwork, pointing, readerings, floor screeds and granolithic toppings. Reduces the overall cost of the work.

#### WHAT IT DOES

When mixed in brich-laying and plastering mortars "Flo-Mix" allows all the time to be omitted, or the commot content to be reduced, consequently reducing the cost of materials. The plasticity and worhability of the mortar are greatly improved and work speeded up. Brichlayers lay more bricks per day, and plasterers can increase the area of rendering carried out. Mertart containing "Flo-Mix" are much more durable than unireated mortars. The mortar is also made rain-proof and is less likely to crack or crase.

Supplied in 5 gall, drums (non-returnable) and 40 gall, drums (returnable). In Liquid form roady for use

Manufactured by:-

ALLIED BUILDING COMMODITIES QUEENS MILL ROAD, FOLLY HALL HUDDERSFIELD TEL: HUDDERSFIELD 2901



#### rent Grave 10.000 tons per week

Washed & Crushed | in. to 1 in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Sand for samples and prices.

#### TRENT GRAVELS LTD

ATTENBOROUGH
Talephone: Nottingham 25-4255

"CONCRETE

#### ROOKZ ON CUI

For a complete catalogue giving price starling and dollars, send a postgard

CONCRETE PUBLICATIONS, Ltd. 14 Dartmouth St., London, S.W.1

**GLASS FIBRE** 

## LIGHTWEIGHT MOULDS

for all

**Concrete Castings** 

I FLOORING

**I STAIRWAYS** 

I PANELLING

**I COLUMNS** 

Our wide experience in catering for moulds for concrete constructional work of every kind has proved that a glass-fibre mould can be produced which is not only equal in strength to a mould made of any other material, but has additional advantages in producing an excellent surface finish, easier handling, and adaptable to any design.

ALL YOUR MOULD PROBLEMS SOLVED



D. A. MODELS LTD

108 WOODSTOCK ROAD LONDON W.4 TEL: CHISWICK 2011

#### maximum light minimum cost LITER roof lights give a very high transmission


of light-up to 92%-and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.



LITEX spherical roof lights

LAMINATED FIBREGLASS roof lights

LITEX roof lights with their glass fibrs reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.



LITEX rectangular roof lights

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.

LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITER roof lights please write to

LITEX lantern lights

LENSCRETE LIMITED Queens Circus London SWS telephone MACaulay 1063

TIMUS SPECIALIST

WM. MULCASTER

& CO. (CONTRACTORS) LTD.

We invite inquiries for Gunite Linings and Renderings for new or old structures of every kind in any part of the country.

HASLINGTON

Telephone : Crewe 2265-6

CREWE



Readymix

#### CONCRETE

was chosen by

TOKEN CONSTRUCTION

CO LTD

for the

LONDON HILTON HOTEL

28 Stories high, the London Hilton, when completed, will be the tallest hotel in Britain. Over 40,000 cubic yards of "Readymix" Concrete will be required to assist the Contractor to maintain his schedule.

Recently 1185 cubic yards of "Readymix" were supplied to the site in less than 12 hours, thereby achieving the largest concrete pour in this country on a building site of this type in a single day.

" Readymix " can be the answer to your concreting problems also.

#### READY MIXED CONCRETE LTD

Head Office: 2 THE SANCTUARY LONDON SWI

Telephone: Abbey 7700

The largest international Ready Mixed Concrete Group in the World.

Plants Throughout The Country.







## REINFORCEMENT SERVICE including SUPPLY & BENDING

We are manufacturers of mild steel bars for reinforced concrete, and have every facility for supplying bars cut to required lengths. We also bend ready for fixing if desired for contracts in any part of the country. Include our name on your list for future reinforcement requirements.

#### WALKER WRIGHT & CO. LTD

DARNALL, SHEFFIELD, 9

TELEPHONE: 41063-4-5



### 3 DEPENDABLE SERVICES FOR YOUR CONTRACTS IN

BEDFORDSHIRE · BERKSHIRE · BUCKINGHAMSHIRE · CAMBRIDGESHIRE

DERBYSHIRE · HERTFORDSHIRE · LEICESTERSHIRE · LINCOLNSHIRE

MIDDLESEX · NORTHAMPTONSHIRE · NOTTINGHAMSHIRE

OXFORDSHIRE · WARWICKSHIRE

## of BEDFORD

for supplies of CONCRETE AGGREGATES

We supply the best washed and graded aggregates and sand, provide an excellent delivery service to your schedule, and give immediate attention to all requirements.

## of BEDFORD

for supplies of PRECAST CONCRETE

Well-matured stocks of concrete kerbs, fencing posts, paving slabs, lintels, cycle blocks, etc., are always available for prompt delivery in any quantity.

## of BEDFORD

CONCRETE BUILDING BLOCKS


Standard concrete building blocks of excellent quality can be supplied by us ex-stock in any quantity—large or small.

CALL HOWARD LTD


ST. JOHN'S WORKS, BEDFORD. TELEPHONE: 4204-6

## THAMES

smooth shuttering without oiling









Noilply moulds for 130 ft. run of floor and roof beams made for the Mersey Dock and Harbour Board, Liverpool. Manufactured by: MILBANK FLOORS LTD, GREAT WALTHAM, CHELMSFORD, EMEX.

Thames Noilply gives the smoothest surface of any shuttering entirely without oiling. This important saving in oil and labour has been achieved by facing the plywood shutter with a special glossy plastic which completely repels concrete and leaves surfaces superbly smooth. With reasonable handling Noilply shuttering can be used time and again without oiling. Later, it continues to give long service in the traditional way. The reverse side is balanced by a standard plastic. Try Noilply on your next contract and see how quickly it repays its cost.

Supplied only through trade channels.


THAMES - NOILPLY

THAMES PLYWOOD MANUFACTURERS LTD

Harts Lane · Barking · Essex · Telephone: Rippleway 5511

98 4194

#### LONGER ...



Main Contractors: Messes. Leonard Fairclough Limited.

#### AND LONGER ...

... and longer. Total length 130 ft, and one of a number produced for the Chief Civil Engineer, British Railways, Euston.

Whatever the size, be it larger or smaller, the same technique is combined with modern methods to produce each concrete unit, manufactured by:

#### ANGLIAN BUILDING PRODUCTS

LIMITED

Designers and Manufacturers of Reinforced and Prestressed Concrete Units

ATLAS WORKS LENWADE NORWICH LONDON OFFICE: 100 BROMPTON ROAD - SW3



#### IN CONCRETE ROAD CONSTRUCTION

Recommended qualities for concrete work are used No. 40 to ass 1521/1949 Class B and tusco No. 60, the choice depending on the streams involved. The former fully meets the specification at the lowest possible cost. As well as preventing sespage from the mix tusco also checks the upward penetration of harmful acids and other chemicals frequently occurring in subscalls. It also has useful applications as a curing overlay. There is no free bitumes in instend to sweat out under exposure to het sun. We will gladly seed samples on request.


For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on IBECO... Like no other waterproof paper, IBECO is waterproof throughout its texture. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair IBECO's impermeability... It's easy and quick to handle—speeds the work as well as lowering its cost and ensuring a better job.

Remember IBECO for contracts in hand and in prospect.

#### DAVIDSONS PAPER SALES LTD.

LONDON: 82/84 St. John St. E.C.1 LIVERPOOL: 31 North John St. 2. LEEDS: 9 Albion St. NEWCASTLE: 42 Corporation St. GLASGOW: Laird Place, Bridgeton, SE. EDINBURGH: Boroughloch Square. DUNDEE: 24 Lamb's Lane. ABERDEEN: 4 Trinity Quay.

HEAD OFFICE: Mugiemoss Mills, Bucksburn, Aberdeen.



IN THE FIELD AVIATION

CONCRETE BEAMS

Hanger for Field Aviation at Toronto International Airport.

Contractors: Community Enterprises Ltd. Consultants:

Consultants: W. S. Atkins & Associates Ltd., Toronto.


Structural Concrete; frame and roofing: Manufactured and erected by Standard Prestressed Structures Ltd., Mable, Ontario. need only one VERTIGAL support to cover 40,000 sq. ft. of floor area

Prestressed concrete provides the Architect with a medium which has many advantages; flexibility in design, speed of construction and structural strength. These advantages are readily demonstrated in the construction of this Malton Hangar where a single column is the sole support within the building. Costs were reduced by the beam design which reduced the area of roofing material and the speed of erection of the framework which only took one week. When you think of prestressed concrete, think of RYLANDS Wire or Strand.

RYLANDS

DEPENDABLE IN THE WORLD OF WIRE

BROTHERS LTD . WARRINGTON . ENGLAND



Contractors: Messes, Holst & Co. Ltd.

To render the ground floors in their new warehouse at Grimsby, hard, dustless, water-proof and able to withstand exceptionally heavy wear and tear, British Titan Products Co. Ltd. chose Lillington's No. 1 Metallic Liquid—a veritable titan amongst proofers.

From 5/- per gallon

SPECIAL TERMS FOR BULK CONTRACTORS

Write for Booklet 56

All our products now sold in free containers

For fifty years, architects have specified Lillington's No. 1 Metallic Liquid, the scientifically prepared admixture that renders concrete completely waterproof and dustless and accelerates setting time.

No. I Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on it to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.


TILLINGTON'S

Nº 1 Metallic Liquid

GEORGE LILLINGTON & CO. LTD. WILLOW LANE, MITCHAM, SURREY

Tel: MITcham 1066

For Scotland: 42 High Street, Greenock. Tel: Greenock 20175



#### CONCRETE BY PUMP AND PIPELINE

Specifications:

Two Sizes	P.C.3	P.C.4
Capacities per hour, approx Range:	20-24 cu. yd.	8-10 cu. yd.
Horizontal, approx	1500 ft. 135 ft.	1250 ft. 125 ft.
Pipeline	6" i.d. 45 h.p.	44" i.d. 25 h.p.

#### **FOR HIRE**



THE REGISTERED TRADE MARK OF THE CONCRETE PUMP COMPANY LIMITED

#### PUMPCRET HIRE COMPANY LTD


4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546.

Telegrams: Pumpcret, Kens, London

## AB MOULDS

CAN BE RELIED UPON TO GIVE CONSISTENT SERVICE OVER MANY YEARS



The above illustration of a standard garden edging mould shows the tough construction of our moulds, which reduces expenditure on maintenance and constant replacement of moulds of less robust design.


#### A. B. MOULD & CONSTRUCTION CO., LTD.


VULCAN WORKS, VULCAN WAY NEW ADDINGTON, SURREY

Telephone: Lodge Hill 2347

Telegrams: Abmould, Croydon

TRUCK MIXERS





Available in several capacities, either with petrol or Diesel engine or power take-off.

Quick and intensive mixing.

Quick charging and discharging.

DEJONG

HAZERSWOUDE HOLLAND

P.O. Box 88 LEIDEN

Over 40 years' experience in the construction of contractors machinery.



\* Industrial buildings designed, supplied and erected by

#### ITHIC CO. LIMITED

REINFORCED CONCRETE INDUSTRIAL FLOORS RECONSTRUCTED STONE

ESTABLISHED 1840

LONDON ADDRESS: 14 College Road, Harrow. Tel: Harrow 6161-2-3 BIRMINGHAM: Northcete Road, Stechford. Stachford. 3831-2. EXETER: 6-8 Melbourne Street. Exeter 73948. EDINBURGH: 48 Duff Street, Den 1361-3. MANCHESTER: Ashton Road, Bredbury, Stockport. Woodley 2877-4.

Ensure safety with DORMAN LONG Steel Trench Sheeting (Regd. Design No. 850,839) The ideal for temporary lining,

easy to drive: can be used over and over again

PROMPT DELIVERY Prices and full particulars on application to

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH London Office: Terminal House, 52 Grosvenor Gardens, S.W.I



### COROBA

COLD WORKED HIGH TENSILE REINFORCEMENT

#### MILD STEEL & HIGH TENSILE WELDED FABRIC

AN EFFICIENT SERVICE ASSURED IN SUPPLY, BENDING & FIXING

#### THE ENGINEERING DESIGN & CONSTRUCTION COMPANY LIMITED

REINFORCEMENT SPECIALISTS

OFFICES: ARDSHIEL HOUSE EMPIRE WAY


WEMBLEY

MIDDX.

TELEPHONE: WEMBLEY 9474

TELEGRAMS: EDCON WEMBLEY

## You get the lowest relaxation using SOMERSET STABILIZED Prestressing Wire



COMPARATIVE RELAXATION GRAPH Initial Stress 80 tons/sq. in.
(Drawn wire in the stress relieved and stabilized condition)

- ★ Somerset Wire complies with B.S. 2691
- \* Is available in plain, indented or helically crimped forms
- \* Has stable elastic characteristics

STABILIZED by a patented 'Somerset' process

SOMERSET WIRE COMPANY LIMITED



Pengam Moors, Cardiff (Cardiff 37485) Bridgwater, Somerset (Bridgwater 3001) MIIII

## Efficient compaction

With frequencies up to 10, 650 full impulses a minute, the Winget 'Vibrocon' range of Poker Vibrators will compact the widest range of mixes with the utmost efficiency and economy. Range of five sizes.

ROCHESTER, KENT





#### ... Precast Concrete Piles

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used. In standard sizes—12" × 12" (in lengths 15 ft. to 40 ft.) and 14" × 14" (lengths 15 ft. to 55 ft.). Other sizes made to order.

STANTERPILES

Write for full details

STENT PRECAST CONCRETE LTD

Chequers Lane, Dagenham Dock, Essex. DOM 0971 (4 lines)

#### SCHMIDT



#### CONCRETE TEST HAMMER

for immediate non-destructive determination of compressive strength

O. A. VOLKMANN
3 ST. AUGUSTINE'S ROAD,
BIRMINGHAM, 16
Telephone: Edgbaston 1353

Best Quality
CONCRETE
AGGREGATES
in all grades

DELIVERED BY ROAD OR RAIL

## WM. BOYER

MEMBERS OF S. & G.A. of G.B.

IRONGATE WHARF, PADDINGTON, W.2
TELEPHONE: PADDINGTON 2014-8

#### DURAJOINT

(Expansion Joint)



ls so easy to Weld



All you need is

- I. A sharp knife
- 2. Pieces of wood
- 3. A blow-lamp or brazier
- 4. Emery cloth or wire brush



Unskilled workers can acquire the "knack" in no time on all types of welds.

AND YOUR WATERSTOP IS COMPLETE WITH NO WASTE OF TIME OR MATERIAL

Sole Manufacturers

#### **DURATUBE & WIRE LTD**

CENTRAL WAY (FAGGS ROAD)
FELTHAM MIDDLESEX

Phone: FELTHAM 3453/6


## concrete cubes on site MILBANK-WELLS

HYDRAULIC PRESS
AND CUBE MOULDS

Immediate Delivery

Two Sizes: 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for

Contract

ALL OVER

6-IN. PRESS

4-IN. PRE

#### MILBANK FLOORS LTD

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Coine 410



### PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft



SINGLE SPAN . MULTI SPAN . CANTILEVER



The first building to be erected in the S.E. corner of the Gatwick Airport which has been developed as a maintenance area, is a 282 ft long, 112 ft wide and 41 ft high hangar for Transair Limited. The hangar is remarkable for its roof structure; notably the inter-connected 110 ft triangular precast and prestressed space frames which span the width of the building. At the front of the building, over the hangar doors, a 10 ft deep main beam was formed by fitting additional

#### Hangar Construction at Gatwick

Sponsor: Transair Ltd.
Architects: Clive Pascall and Poter Watson.
Design and erection of structural frames:
The London Ferro-Concrete Company Limited
in association with A. J. and J. D. Harris.
Consulting engineers for the prestressed concrete apron:
A. J. and J. D. Harris.

General Contractors for building and apron: Sir Alfred McAlpine and Son Limited. members between the ends of the secondary beams. The beam is continuous and supported by three prestressed concrete columns to provide two clear spans of 140 ft. The columns were prestressed on the Freyssinet system to support bending moments due to horizontal wind forces. The major prestressed force for the main beam was applied on the Freyssinet system. A leaflet giving comprehensive details of the complete project is available on request.



wire was essential-

Johnsons. of course!

Richard Johnson and Nephew Ltd. Manchester 11. Telephone: EASt 1431




Illustration above shows some of the post-stressed bridge beams, each 80 ft. long and weighing 35 tons, produced by Anglian Building Products Ltd., for British Railways, Midland Region. Main Contractors: Messrs. Leonard Fairclough Ltd.

## cast in WOODEN MOULDS

supplied by

## MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9

ON



## PLACRETE

AID FOR A WELL-DESIGNED CEMENT MIX

#### PLAZGRETE RETARDS THE SET

Permits longer haulage time Avoids day joint problems

#### PLAZGRETE IMPROVES WORKABILITY AND PLASTIGITY

Makes pumping easier Saves time placing and vibrating Improves consolidation, particularly around reinforcement

#### PLAZGRETE PERMITS A REDUCED WATER/ CEMENT RATIO

Reduces shrinkage Eliminates laitence, bleeding and segregation

PLAZGRETE IN THE MIX REDUCES THE COST WITHOUT ANY LOSS OF STRENGTH

For further information write to Dept. PC.:

#### SEALOCRETE PRODUCTS LTD.,

ATLANTIC WORKS, HYTHE ROAD, LONDON, N.W.10.

Telephone: Ladbroke 0015, P.B.E. Telegrams: Sealocrete, Wesphone, London.

N.B. When retarding of the set is not required Plazcrete (Non-retarding) can be supplied.



#### Boosting storage space capacity—the high-speed HYSTER truck moves and stacks faster and more smoothly.





Hyster SpaceSaver Lift Trucks from 1,000 lb. to 10,000 lb. capacity: Challenger Lift Trucks from 1,000 lb. to 46,000 lb.; diesel, L.P.G. c petrol. Hyster Ransomes-Electric Lift Trucks from 1,000 lb. 1 6,000 lb.capacity, with complementary range of cranes, towing tugs, platform trucks, reach trucks, straddle trucks, hydraulic and mechanical attachments.

"Hyster" and "Space-Saver" are Registered Trade Marks

The Authorised Hyster Dealers

LEVERTON (Individual) LIMITED Mandawbank Road, Rollharham, Telephona: Notherham 78233 Branch deants, Nancastle, Wiger and Septeme.

A. H. MASSER, LIMITED East Wall Road, Dublin, 3. Talaphone: Dublin 79801

21, Old Castle Road, Glasgow, S.A. Telephone: Marrylae 2253/4


FRED MYERS LIMITED 24, Bruton Street, London, W.I. Telephone: Hyde Park 6915 J. E. COULTER LIMITED 38-56 Mitthald, Butlant, S. Talaphore : Beifast 364744

## HILTON GRAVEL

SEVEN PITS

250 LORRIES

8,000 TONS PER DAY



### FOR QUALITY & SERVICE

REGULAR DELIVERIES THROUGHOUT

STAFFORDSHIRE

DERBYSHIRE .

WEST RIDING

SHROPSHIRE LEICESTERSHIRE

CHESHIRE

NOTTINGHAMSHIRE

LANCASHIRE

WARWICKSHIRE RUTLAND

The illustration above shows one of our seven pits equipped with the most modern washing and grading plant for producing concrete aggregates that will satisfy the most exacting requirements for cleanliness and grading to specifications.

READY MIXED CONCRETE


20 miles radius MANCHESTER

From our Plant

RICE STREET
MANCHESTER 3

DEAnsgate 5455

HILTON GRAVEL LIMITED
HEAD C FFICE: HILTON, DERBY, Tel: ETWALL 422



#### **OUTSTANDING BUILDING...**

#### Outstanding Products

CHEMICAL
BUILDING
PRODUCTS LTD
Warple Works
Cleveland Road
Hemel Hempstead
Herts

Telephone:
BOXMOOR 4900
(5 lines)
Telegrams: Prolithu
Hemel Hempstead

PROLAPIN Liquid Cement Waterproofer
LITHURIN Concrete Floor Hardener
QUICKSOCRETE P. Q. & D. Rapid Hardeners
and Setters

WETEXI'S' Colourless Silicone Waterproofer
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CONBEX Plasticised Expanding Grouting Material
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
ROAD CONPLAST Air Entrainer and Plasticiser
LIFTOYL Floor Cleaner and Degreaser
ORKIT & TEKTAM Bituminous Coating and
Compounds

CONCURE Concrete Curing Agent
NITOLUX & ROBRITE Paints

NEW!! SCREEDEX the ideal Screed Additive.

CHEMICAL BUILDING PRODUCTS LTD

Constructional Skill and Ability:

ONCRETE CONTRACTOR

Monk have been associated with some of the biggest names and biggest projects in the country. What is more - new clients quickly become old friends, and many old friends are of very long standing indeed. There can be no better testimonial to Monk efficiency and reliability.

The high reputation of Monk is built on many factors - among them progressive methods, smooth control of jobs, high quality and — most important — completion on time. It is more and more the practice today for clients to call in Monk at the planning stage and so benefit from their wide experience right from the start. If you have a new project in mind, it would pay you to call in Monk NOW.



A. MONK & COMPANY LIMITED

Warrington and London Offices at: Hull, Middlesbrough & Stamford CEI FOR Z E œ 48 (5) Z 8 e. RIN 33 GIN EN

5



The water tower illustrated has a protective Stic B stone covering stipple finish similar to that shown in the smaller photograph. Treated in this way it is completely protected from the atmosphere and will require no further attention for many years. Stic B can

be applied direct to new or old concrete and most other building surfaces. No other material affords such lasting protection, while remaining so easy to apply.

Descriptive literature available.

### STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD.

VAUXHALL, S.W.B


Telephone: RELiance 5566/2178 Telegrams: Sticheelim, London, S.W.8



Today's basic constructional material is concrete. It is used in roads, offices, factories, warehouses, and every conceivable kind of building. But to do its job with complete efficiency, concrete must be strengthened. And this is where Spencer Mesh comes in. Made to B.S. requirements, this electrically-welded mesh is made only from high tensile steel wire. Strong. Reliable. And what is more, the wire is drawn by the Spencer Wire Company themselves, in their own mill. Spencer Mesh is supplied in standard square or oblong meshes, in either sheets or rolls. If you have a concrete reinforcement problem, get in touch with the Spencer Mesh people. You can be sure of really useful help.

## SPENCER MESH

SPENCER WIRE . WAKEFIELD Telephone Wakefield 6111



THORESBY

CONSTRUCTION OF NEW FAN DRIFT AND MOTOR HOUSE EXTENSION.

J. A. WHITAKER
B.Sc., A.M.I.C.E
Divisional Civil Engineer
National Coal Board,
East Midlands Division



for

## REINFORCED CONCRETE CONSTRUCTION

HEAD OFFICE: HAYDN ROAD, SHERWOOD, NOTTINGHAM

Telephone: 66264 (10 lines)

LONDON . MANCHESTER . BIRMINGHAM . LEEDS

Overseas Branches: ADEN · TORONTO



Now fitted with overload and anti-single-phase switches.

This new internal vibrator dispenses with the use of flexible drives. It has a frequency of 12,000 r.p.m. which, combined with amplitude, provides exceptional compaction of very harsh mixes. Vibrators of varying sizes, together with single- and multi-tool generators (Petrol, Diesel, and Electric drives), make this the most versatile range of Internal vibrators so far available. It is in full production, and has already proved of considerable value to Contractors, Builders, and Precast Concrete Makers. Complete details of these and the range of Allam Vibrating Equipment will be sent on request.

#### E.P.ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1. . Telephone: Sloane 9976 (5 lines)

Works: Southend-on-Sea Tal.: Eastwood 525243

AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altrincham, Ches.; O. L. Davies, Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Berslem, Stokk-oo-Trent; Concrete Engineering Services, York Read Industrial Estate, Wesherby, Yorks; John Redistone Ltd., Newcastle-on-Tyne; W. R. Selwood Ltd., Chandler's Ford, Southampton; J. A. McAra & Co. Ltd., Ghasgow; Modern Plant Sales Ltd., Oldbury, Birmingham.

from every aspect, the finest equipment

PORTA

FOR SITE HANDLING OF BULK CEMENT

ORTASILO LI ED - Home Seles Office: LAWRENCE LOAD REEN LANE - UNSLOW - MIDDLESS) Telephone Man w 6452/3

HEAD OFFE ORK . Y at BIRMINGH . MANCHESTER

Write or phone today for details of full range of equipment

## **ICRET** CTIONAL ENGIN

INCLUDING PRESTRESSED CONCRETE

Volume LVI, No. 7.

LONDON, JULY, 1961.

#### EDITORIAL NOTES

#### Structural Safety.

British Standards are too severe. Dams burst and cranes collapse. These are some of the contrary opinions expressed at a recent conference(1) on standard specifications. The view that the requirements of some British Standards, which in other quarters have been referred to as standards of mediocrity, could well be made less stringent raises the whole question of factors of safety. In this connection the extract from an introductory note in a new book (2) on foundations.

which is given in the following, is apposite.

"In theory the factor of safety is the 'strength' of the structure divided by the loading. Since both these values in practice are stochastic (3) the result can only be statistically assessed within some arbitrary parameter. What is often miscalled the 'factor of safety' is the ratio between the 'strength' as calculated by one arbitrary Code of Practice and the loading stipulated by another arbitrary Code. Since these Codes vary from one edition to another and since there is no statutory guarantee that their compilers know what they are codifying. this ratio is variable and no more reliable than the opinions of those members of the drafting committee who were not too busy to take an active part in the drafting. Any interpretation must depend eventually on personal interpretation of what is 'reasonable risk' which involves a consideration of the results of structural failure. To suggest that the lead in a pencil should be heavily reinforced to eliminate breakage is ridiculous since the consequential damage is infinitesimal. If the draughtsman was severely injured every time his pencil point broke it would be quite a different matter. Was it reasonable to suppose that the Dutch and English coast defence works that had stood for a century were 'reasonably' safe the day before they were overtopped in 1953? We now know that the dam near Fréjus (or its foundations) had a factor of safety of less than unity. How many experts were satisfied that it was 'reasonably' safe a week before failure occurred? It is clear that any structure whose failure must involve wholesale

<sup>(1).—</sup>Seventh Standards Engineers' Conference held in London, May 1961.
(2).—"Design and Construction of Foundations." By G. P. Manning, M.Eng., M.I.C.E.
(3).—"Stochastic" = pertaining to conjecture (O.E.D.); but now used in statistics to indicate some degree of randomness.

loss of life should have a larger factor of safety than one whose failure involves only petty annoyance, but what limits should we set? If we can increase the calculated factor of safety by 50 per cent. at a cost of only 5 per cent. increase in expenditure the decision may be easy, but if the cost increases 75 per cent. it may be difficult. In doubtful cases the engineer should estimate what an increase in the strength of the foundations would cost and how this would compare with the total final cost of the whole building since failure of a foundation involves everything above it.

Between the years 1909 and 1959, the allowable stress in mild steel in the London area has increased from 7½ to 10 tons per square inch (and now presumably to 10½ tons) while the assumed imposed load on an office floor has decreased from 100 to 50 lb. per square foot, representing a mental readjustment of 180 per cent. Is a factor of safety then, to the official mind, only a matter of opinion? If a bearing pressure of 2 tons per square foot was considered reasonably safe on a certain type of ground in 1909 under an office building assumed to carry an imposed load of 100 lb. per square foot, should we limit the pressure to 1.5 tons per square foot if we now calculate for loads of only 50 lb. per square foot?

If the mechanical engineer estimates that his plant will weigh 50 tons, he may, if naturally timid or doubtful of the structural engineer's ability, increase this weight to 75 tons or even 100 tons. If the engineer for the superstructure mistrusts both the mechanical engineer and the foundation engineer he may pass this on as 150 tons. If the foundation engineer also has his doubts he may design the foundations to carry 200 tons. If the mechanical engineer's estimate of 50 tons is correct and if the foundation engineer correctly assesses the allowable bearing pressure we have a factor of safety of about ten.

The only factual step towards establishing a value for the factor of safety is to test-load the finished structure. After that we still, in most cases, do not know what maximum load the structure may reasonably have to carry during its effective life (after having, of course, determined how long its effective life can reasonably be expected to last). Would it now be reasonable to include in our estimated loading the risk of the superstructure being struck by an artificial satellite?

The disaster at Fréjus presents also the other side of the argument. Apparently the Roman amphitheatre withstood the onrush of water while modern buildings collapsed. Apart from emphasising the superb technique of the Roman engineer, was the designer of this building grossly extravagant in providing a structure that outlasted its useful life by x500 years? He could scarcely have foreseen that it would prove a source of attraction to tourists two thousand years after his death."

The causes and prevention of structural failures was the subject of a paper entitled "The Pathology of Construction" presented last month by M. Albert Brenier at a joint meeting of the Institution of Structural Engineers and the British Section of the Société des Ingénieurs Civils de France. The theme of the paper was that it is better to build soundly thereby avoiding damage than to have to seek remedies which are often no more than palliatives to incurable ills. This was the basic idea behind the creation in 1929 of the Bureau Securitas of the French department of public works, the mission of which was to prepare regulations principally for structural calculations and to supervise construction. The



regulations have been revised from time to time, the latest regulations for reinforced concrete being issued in 1960. Similar codes for prestressed concrete are being prepared. Supervision to prevent failures, however, constitutes the basic activity of the Bureau, and an offshoot, the Société de Contrôle Technique et d'expertise de la Construction, has been established. The means taken for the prevention of failures has enabled architects, engineers and contractors to insure against the consequences of their responsibilities. In France, this responsibility is heavy since the Civil Code, which dates from Napoleonic days, requires the guarantee of structures against the ruin of part or the whole of a structure for a period of ten years. The notion of ruin has been extended considerably by the courts to include lesser defects short of collapse.

From the numerous investigations made by the Bureau and its successors an extensive documentation has been compiled and leaflets relating to instructive cases of failure are published. The technical examination of failures of foundations or superstructures is of great importance since failures are true full-scale

tests to destruction.

#### Ready-mixed Concrete.

The popularity of ready-mixed concrete is growing considerably. Its use is today by no means confined to building sites in cities where in this country, for at least three decades, it has been acknowledged as a convenient form of supply, mainly because it is necessary for one vehicle, that is the mobile agitator or mixer, to traverse the streets instead of several vehicles delivering aggregates and cement. Before World War II, there were barely half-a-dozen firms supplying ready-mixed concrete, but in 1961 there are upwards of one hundred and thirty. In 1951, the seven members of the British Ready Mixed Concrete Association produced about 187,000 cu. yd., but in 1960 the membership of the Association had increased to about eighty and their output had increased to nearly five million cubic yards.

On extensive works such as roads and motorways, it is not uncommon for the concrete to be batched or mixed at a central point and distributed in mobile mixers or agitators. However, in districts remote from cities or sites of large works, many ready-mixed concrete plants have been installed, generally near aggregate pits or quarries, from which concrete is supplied to large and small constructional works in the neighbourhood. Some of the plants, such as those newly installed plants described elsewhere in this number, are highly mechanised. Others, such as one at Fulham (see this journal for October 1960) which produces up to 1500 cu. yd. daily, have high productive capacities. What is probably the world's record output is that of a plant in Montreal, Canada, which, as reported at the annual convention of the National Ready Mixed Concrete Association (U.S.A.) held at Miami Beach in January last, has a capacity of 300 cu. yd. per hour.

Parallel to the growth of the use of ready-mixed concrete in Great Britain is the corresponding development of mobile mixers, and some new vehicles of this

type are described on page 263 of this number.

#### Book Reviews.

"Prestressed Concrete Simply Explained." By H. Kaylor. (London: Contractor's Record Ltd. 1961. 28s.)

THE implication in the title of this small book is well maintained in the clearly written text which is based mainly on the two current British Standard codes of practice dealing with prestressed concrete. There is, however, much material additional to, or in amplification of, the codes. Some, but by no means all, of the systems of prestressing available in this country are described. Some of the examples give solutions of a problem by the adoption of two or more systems. Another feature of the descriptive numerical examples is that in many cases any formulæ used are repeated in the example with an explanation of the symbols. More consideration could be given to the design of the ends of beams; but the solitary reference to this subject in the index does not do justice to the few references in the text.

Since the volume is evidently meant as a book for beginners, it may seem out of place to include general illustrations of extraordinary structures such as the water tower at Örebro and the exhibition hall in Paris; detailed descriptions with drawings of more usual simple works would be

advantageous.

"The Geometric Design of Modern Highways." By J. H. Jones. (London: E. & F. N. Spon Ltd. 1961, 635.)

THE claim that this book is an attempt to interpret American and Continental practice in highway engineering in terms of the special requirements of Britain's programme of road construction is well based except that the author has not troubled in all cases to translate American terms into their English equivalents. Much of the subject matter is no doubt in the province of that new breed of practitioners, namely, traffic engineers, as is seen from the contents which include the principles of highway design, horizontal and vertical alignment, cross-section of roads, sign-posts, markings on carriageways, junctions, separation of carriageways, and the analysis of the designs of existing roads. There is nothing on the actual construction of roads.

"Papers Presented at the Third Infernational Congress of the Precast Concrete Industry." Stockholm, 1960. (London: Distributed on behalf of the British Cast Concrete Federation by Concrete Publications Ltd. 1961. Main Papers and Reports £3 3s. post free; in Canada and U.S.A. 15 dollars. Main Papers and Reports with Supplementary Papers and Reports £4 4s. post free; in Canada and U.S.A. 20 dollars.)

THE papers and reports presented at the Third International Congress of the Precast Concrete Industry, held in Stockholm in 1960, are collated in this publication, which is in the English language and in loose-leaf form in a substantial binder. The publication is in two editions, one containing the reports and main papers only and the other the reports and main papers together with supplementary

papers and reports.

Although the subject-matter is primarily of interest to the precast concrete industry. many of the papers such as those dealing with vibration, shrinkage and structural precast concrete are of value to other branches of concrete engineering. contents also include papers dealing with concrete pipes, and in particular the protection of pipes against aggressive soils and waters, plastic coverings and ocrafe methods. Psychosociological problems associated with human relations in the products industry are also considered. The subjects of the supplementary papers and reports include precast concrete shells, bridge construction, flues, beams with high-strength reinforcement, electrical curing, and the concrete block industry.

#### Books Received.

"Constructional Engineer." By E. Leyland. [London; Edmund Ward (Publishers) Ltd. 1961. Price 9s. 6d.]

lishers) Ltd. 1961. Price 9s. 6d.]

"Graphic Statics." By C. S. Benson.
(London: B. T. Batsford Ltd. 1961.
Price 25s.)

"Industrial Architecture." By J. F. Munce. (London: Iliffe Books Ltd. 1961. Price £5 5s.)
"Motopia." By G. A. Jellicoe. (London:

Studio Books, Longacre Press Ltd. 1961.

"The Business of Management." By R. Falk. (London: Penguin Books Ltd. 1961. Price 3s. 6d.)

#### Balcony Slabs Spanning in Two Directions.

By L. S. MÜLLER.

The accompanying tables apply to the design of two common cases of balcony slabs, namely, rectangular panels fixed on three sides and unsupported on the fourth, and rectangular panels with two adjacent sides fixed and the other two sides unsupported. The tables are based on the yield-line method.

#### Rectangular Panel Fixed on Three Sides and Unsupported on one Side.

CASE I.— $z \le L_x$ : yield-line pattern and notation as in *Diagram* I, *Table* I. Also q = total load, n = factor of safety required, and  $q_{\text{or}} = nq = \text{critical load}$ .

The virtual external work of the load in the stage when the yield-lines develop may be expressed as follows.

$$U_{e} = \left[\frac{L_{yz}}{2 \times 3} + \frac{2L_{yz}}{2 \times 2 \times 3} + \frac{2(L_{z} - z)L_{y}}{2 \times 2}\right]q_{er} = \frac{L_{y}q_{er}}{6}(3L_{x} - z). \quad (1)$$

If  $m_x$ ,  $m_y$  are the bending moments per unit length in the span,  $m_x'$ ,  $m_y'$  the support bending moments along yield-lines in the directions x and y, the virtual internal work of the yield-moments is  $U_i = \frac{4Lx}{L}(m_y + m_{y'}) + \frac{Ly}{L}(m_x + m_{y'}).$ 

Assuming arbitrarily that  $m_s = m_y$  and  $m_{s'} = m_{y'} = 2m_y$ ,

$$U_i = \left(\frac{12L_x}{L_y} + \frac{3L_y}{x}\right)m_y$$
. . . . . (2)

Equating (1) and (2)  $U_{\theta} = U_{i}$ , from which

$$q_{\rm cr} = \frac{6}{L_{\rm y}^2} \cdot \frac{12L_{\rm z}z + 3L_{\rm y}^2}{3L_{\rm x}z - z^2} m_{\rm y}. \qquad (3)$$

The critical load is when this is a minimum, that is when  $\frac{dq_{cr}}{dz} = 0$ , and for this con-

dition  $4L_zz^2+2L_y^2z-3L_zL_y^2=$  o. Solving for z, and denoting  $\frac{L_y}{L_z}=\lambda$ ,

$$z = \frac{\sqrt{12 + \lambda^3} - \lambda}{\lambda} L_y = \beta L_y.$$
 (4)

The boundary of validity is when  $z \le L_x$ , which gives a maximum value of  $\lambda$  equal to z. Substituting in (3),  $z = \beta L_y$ , and solving for  $m_y$  gives

$$m_y = \left[\frac{\lambda^2 \beta(3 - \lambda \beta)}{12\beta + 3\lambda}\right] \left(\frac{q_{cr} L_x^2}{6}\right) = \gamma q_{cr} L_x^2. \qquad (5)$$

Case II.— $2z \le L_y$ : yield-line pattern as in Diagram II, Table I. The virtual external work of the load is

$$U_{\theta} = \frac{L_{x}q_{er}}{6}(3L_{y} - 2z).$$
 (6)

The virtual internal work of the yield-moments is

$$U_4 = \frac{2m_y'L_x}{z} + \frac{2m_x'z}{L_x} + \frac{m_{x'}(L_y - 2z)}{L_x} + \frac{2m_xz}{L_x} + \frac{2m_yL_x}{z}.$$

With  $m_x = m_y$ , and  $m_{x'} = m_{y'} = 2m_y$ 

$$U_4 = \left[\frac{6L_x}{z} + \frac{2(L_y + z)}{L_x}\right] m_y.$$
 (7)

Equating (6) and (7) and solving for qer gives

$$q_{cr} = \frac{12}{L_x^2} \cdot \frac{3L_x^2 + L_y^2 + z^2}{3L_yz - 2z^2} m_y. \qquad (8)$$

TABLE I,-RECTANGULAR PANEL SUPPORTED ON THREE SIDES.

	Ly/La	β	T
4 2.00	0.3	0.7950	0.00316
	0.4	0.7705	0.00529
Z ≦ L,	05	0.7500	0.00781
Z = BLy	0.6	0.7280	0.01063
	0.7	0.7080	0.01367
my= gqcrLx	0.8	0.6900	0.01687
	0.9	0.6700	0.02019
	1.0	0.6510	0.02357
	1.1	0.6345	0.02699
m. Villa	1.2	0.6160	0.03040
my A	1.3	0.6000	0.03380
-my	1.4	0.5845	0.03714
	15	0.5690	0.04044
Lx	1.55	05612	0.04204
	1.6	0.5540	0.04369
/	1.7	0.5400	0.04676
m <sub>u</sub>	18	0.5265	0.04979
MMMMMMMMMM X	1.9	0.5110	0.05273
Ly	2.0	0.5000	0.05556
	Ly/Ls	β	7
Ly ≥ 1.55	1.55	0.7748	0.04169
	16	0.7869	0.04337
$Z \leq \frac{L_y}{2}$	1.7	0.8101	0.04667
Z = BLx	1.8	0.8315	0.04991
	19	0.8513	0 05309
my= gqcrL2	20	0.8695	0.05619
+ + Z +	2.1	0.8869	0.05922
WILL A	2.2	0.9029	0.06218
/ 10	2.3	0.9178	0.06506
/ ina	2.4	0.9318	0.06788
- my	2.5	0.9449	0.07063
	2.6	0.9573	0.07330
lmi.	27	0.9688	0.07591
	28	0.9798	0 07845
Ly	29	0.9902	0.08092
			0.08333

#### BALCONY SLABS SPANNING IN TWO DIRECTIONS.

From 
$$\frac{dq_{er}}{dz} = 0$$
,  $z = \frac{6L_z}{5\lambda}(\sqrt{1 + 1 \cdot 25\lambda^2} - 1) = \beta L_z$ . (9)

The boundary of validity is when  $2z = L_y$ , which gives a minimum value of  $\lambda$  equal to 1.55. Substituting  $z = \beta L_x$  in equation (8), and solving for  $m_y$  gives

$$m_y = \frac{3\lambda\beta - 2\beta^2}{3 + \lambda\beta + \beta^2}, \frac{q_{cr}L_x^2}{12} = \gamma q_{cr}L_x^2.$$
 (10)

Obviously there is an overlap between the two cases between  $\lambda = 1.55$  and λ = 2.0 since the equations of virtual work have been determined for different conditions. What is interesting is that for the factors y within the region of the overlap almost identical values are obtained when computed from either of the yield-line patterns. The values of  $\beta$  and  $\gamma$  for both cases are tabulated as functions of  $\lambda$  in Table I. The greater value of my should be adopted.

#### Rectangular Panel with Two Adjacent Sides Fixed, and the other Sides Unsupported.

Referring to the diagram in Table II, it can be proved that for any value of  $\lambda$  the yield-line denoted by a-a will give a higher value for the critical load than the other pattern shown on the same diagram. Notwithstanding, the slab must be reinforced for the possible yield-line a-a and for the corresponding load as well, otherwise the slab may fail along yield-line a-a before the decisive pattern has developed.

The virtual external work of the load for the decisive pattern may be expressed as follows.

$$U_y = \frac{2L_z z q_{cr}}{2 \times 3} + \frac{(L_y - z)L_z q_{cr}}{2} = \frac{L_z}{2} (L_y - \frac{z}{3}) q_{cr}.$$
 (11)

The virtual internal work of the yield-moments i

$$\begin{split} U_4 &= \frac{m_y ' L_x}{z} + \frac{m_y L_x}{z} + \frac{m_x z}{L_x} + \frac{m_z ' L_y}{L_x} \\ &= \frac{L_x}{z} (m_y + m_y ') + \frac{m_x z}{L_x} + \frac{m_z ' L_y}{L_x}. \end{split}$$

(a).—Assume arbitrarily that  $m_x = m_y$  and  $m_{s'} = m_{y'} = 2m_y$ . Then

$$U_4 = m_y \left( \frac{3L_s}{z} + \frac{z + 2L_y}{L_z} \right).$$
 (12)

Equating (11) and (12) gives  $\frac{L_x}{2} \left( L_y - \frac{z}{2} \right) q_{er} = \left( \frac{3L_x}{z} + \frac{z + zL_y}{L_x} \right) m_y$ .

Solving for 
$$q_{cr}$$
 gives 
$$q_{cr} = \frac{2(3L_x^2 + 2L_yz + z^2)m_y}{L_x^2(zL_y - \frac{z^2}{3})}.$$
 (13)

For the minimum value of  $q_{er}$ ,  $\frac{dq_{er}}{dr} = 0$  from which


Substituting  $z = \beta L_x$  in (13) and solving for  $m_y$  gives

$$m_y = \frac{3\beta\lambda - \beta^3}{3 + 2\beta\lambda + \beta^3} \cdot \frac{q_{cr}L_x^2}{6} = \gamma q_{cr}L_x^2$$
. (15)

(b).—Assuming  $m_x = m_y$ ,  $m_{x'} = 2m_y$ , and  $m_{y'} = 3m_y$ , by the same consideration as before, for the minimum value of qer

$$z = \frac{4}{5\lambda}(\sqrt{1 + 3.75\lambda^2} - 1)L_x = \beta L_x$$
. (16)

TABLE II .- RECTANGULAR PANEL SUPPORTED ON TWO ADJACENT SIDES.



R POSSIBLE YIELD-LINE a-a NEGATIVE REINFORCEMENT FROM EQUATION of the second of the se

Ly/Lx	m <sub>x</sub> - m <sub>y</sub> m <sub>x</sub> - m <sub>y</sub> - 2 m <sub>y</sub>		m <sub>x</sub> - m <sub>y</sub> m <sub>y</sub> - 3 m <sub>y</sub>		
	ß	7	ß	T	2
1.0	0.870	0.0562	0.944	0.0477	0.0833
1.1	0.903	0.0622	0.986	0.0532	0.0913
1.2	0.932	0.0679	1.018	0.0587	0.0984
1.3	0.957	0.0733	1.051	0.0637	0.1047
1-4	0.980	0.0785	1.079	0.0685	0.1104
1.5	1.000	0.0833	1.105	0.0733	0.1154
1.6	1.018	0.0880	1,128	0.0777	0.1199
1.7	1-034	0.0924	1.149	0.0820	0.1238
1.8	1.058	0.0966	1,166	0.0860	0,1274
1.9	1.062	01006	1.1.84	0.0900	0.1305
2.0	1.075	0.1044	1.200	0.0938	0.1333
2.1	1.086	0.1080	1.215	0.0973	0.1359
2.2	1.096	0.1114	1.227	0.1007	0.1381
2.3	1.106	0-1147	1.240	0.1040	0.1402
2.4	1.115	0.1179	1.250	0.1072	0.1420
2.5	1.123	0.1209	1.261	0.1102	0.1437
2.6	1-151	0.1237	1.271	0.1132	0.1452
2.7	1.138	0.1265	1.280	0.1160	0.1466
2.8	1.144	0.1291	1.287	0.1185	0.1478
2.9	1.151	0.1316	1.297	0.1212	0.1490
3.0	1.156	0.1341	1,305	0 1237	0.1500

As already mentioned, a—a is a possible yield-line and, although not decisive for the critical load, reinforcement must be provided for the negative yield-moments caused by it. The moment developed along a—a (Fig. 1) is

$$M_d = \frac{q_{cr}L_xL_yh}{2\times3} = \frac{1}{6}L_x^2L_y\sin\phi.$$
 (18)

From the vector-triangle,  $M_d = M_x \sin \phi + M_y \cos \phi$ , or

$$\frac{1}{2}q_{cr}L_{x}^{2}L_{y}\sin\phi=m_{x}^{\prime\prime}L_{y}\sin\phi+m_{y}^{\prime\prime}L_{z}\cos\phi.$$

Dividing by  $L_x \sin \phi$  gives  $\frac{1}{2}q_{cr}L_xL_y = m_x''\frac{L_y}{L_x} + m_y'' \cot \phi$ . Substituting  $\cot \phi = \frac{L_x}{L_y}$ 




Fig. 1.

gives 
$$\frac{1}{6}q_{er}L_{x}L_{y} = m_{x}''\frac{L_{y}}{L_{x}} + m_{y}''\frac{L_{x}}{L_{y}} = m_{x}''\lambda + \frac{m_{y}''}{\lambda}.$$
 (19)

Since  $\frac{M_x}{M_y} = \tan \phi = \frac{m_x'' L_y}{m_y'' L_x}$ , it follows that

$$\frac{m_{x''}}{m_{y''}} = \tan \phi \cot \phi = I \quad . \qquad . \qquad . \qquad . \qquad (20)$$

that is, it is not possible to choose freely the value of  $\frac{m_x''}{m_y''}$  since they must be equal.

From (19) therefore 
$$\frac{1}{k}q_{cr}L_xL_y = m_y''\left(\lambda + \frac{1}{\lambda}\right)$$
, or, if  $L_y = \lambda L_x$ ,  $\frac{q_{cr}L_x^2}{6} = m_y''\left(1 + \frac{1}{\lambda^2}\right)$ 

and 
$$m_y'' = m_{x''} = \frac{1}{6\left(1 + \frac{1}{13}\right)} q_{er} L_x^3 = \frac{\lambda^3}{6(\lambda^2 + 1)} q_{er} L_x^3 - \delta q_{er} L_x^3$$
. (21)

The factors  $\beta$  and  $\gamma$  for both sub-cases (a) and (b), and the factor  $\delta$  as functions of  $\lambda$  are tabulated in Table II.

Equations (18) to (21) were derived by Mr. A. Zaslavsky, Associate Professor, Technion, Haifa.

#### Examples.

(1) For a rectangular balcony slab fixed along three sides, and unsupported along the fourth side,  $L_y = 8$  ft. 9 in. and  $L_x = 6$  ft. 3 in. The load is as follows.

Assuming 4-in. slab = 50 lb. per sq. ft. Floor construction, plaster, etc. = 30 ,, ,, ,, ,,

Total load 180 ,, ,, ,,

Assume n = 2. The critical load  $q_{er} = 2 \times 180 = 360$  lb. per sq. ft.

$$\lambda = \frac{L_y}{L_x} = \frac{105}{75} = 1.4.$$

From Part I of Table I,  $\beta = 0.5845$  and  $\gamma = 0.03714$ . Therefore

$$z = 0.5845 \times 105 = 61.3$$
 in.

$$m_y = m_x = 0.03714 \times 360 \times 6.25^{\frac{3}{2}} = 523$$
 ft.-lb. per ft. width.  $m_{x'} = m_{y'} = 2m_y = 1046$  ft.-lb. per ft. width.

If the yield-stress of the steel is 36,000 lb. per sq. in. the reinforcement to resist the positive bending moments along yield-lines within the slab with  $d_x = 3$  in. and  $d_y = 3\frac{1}{4}$  in. is  $523 \times 12$ 

$$A_{sx} = \frac{523 \times 12}{0.9 \times 3 \times 36,000} = 0.065 \text{ sq. in, per ft.,}$$

and 
$$A_{sy} = \frac{523 \times 12}{0.9 \times 3.25 \times 36,000} = 0.06$$
 sq. in per ft.

Therefore provide 1-in, bars at 9 in. in both directions.

The reinforcement required to resist the negative bending moment along the support yield-line of length  $L_y$  is

$$A_{sz}' = \frac{1046 \times 12}{0.9 \times 3 \times 36,000} = 0.13$$
 sq. in. per ft.,

and along the yield-lines of length  $L_z$  is

$$A_{4y'} = \frac{1046 \times 12}{0.9 \times 3.25 \times 36,000} = 0.12$$
 sq. in. per ft.

Therefore provide 1-in. bars at 41-in. centres across each support.

(2) Consider a balcony slab of the same size as in Example (1) but fixed along two adjacent sides and unsupported along the other two sides.

Assuming  $m_x = m_y$  and  $m_{z'} = m_{y'} = 2m_y$  from Table II (for  $\lambda = 1.4$ ),  $\beta = 0.98$ ,  $\gamma = 0.0785$ , and  $\delta = 0.1104$ . Therefore

$$s = 0.98 \times 75$$
 in.  $= 73\frac{1}{8}$  in.  $= 6$  ft.  $1\frac{1}{8}$  in.  $m_S = m_W = 0.0785 \times 360 \times 6.25^{\frac{9}{8}} = 1105$  ft.-lb. per ft.  $m_{S'} = m_{H'} = 2m_{H'} = 2210$  ft.-lb. per ft.

$$m_{x'} = m_{y'} = 2m_{y} = 2210$$
 ft.-lb. per ft.  
 $m_{x''} = m_{y''} = 0.1104 \times 360 \times 6.25^{2} = 1555$  ft.-lb.

The reinforcement required to resist the positive bending moment along the

internal yield-line is 
$$A_{ss} = \frac{1105 \times 12}{0.9 \times 3 \times 36,000} = 0.136$$
 sq. in. per ft.,

and 
$$A_{ey} = \frac{1105 \times 12}{0.9 \times 3.25 \times 36,000} = 0.126$$
 sq. in, per ft,

Provide 1-in. bars at 4-in. centres.

The reinforcement required to resist the negative bending moment along supports

is 
$$A_{82}' = \frac{2210 \times 12}{0.9 \times 3 \times 36,000} = 0.272$$
 sq. in. per ft.,

and 
$$A_{ty'} = \frac{2210 \times 12}{0.9 \times 3.25 \times 36,000} = 0.252 \text{ sq. in. per ft.}$$

Provide 1-in. bars at 41-in. centres.

The reinforcement required to resist the negative bending moment along yield-line

a-a is 
$$A_{82}'' = \frac{1555 \times 12}{0.9 \times 3 \times 36,000} = 0.192$$
 sq. in. per ft.,

and 
$$A_{sy''} = \frac{1555 \times 12}{0.9 \times 3.25 \times 36,000} = 0.177 \text{ sq. in. per ft.}$$

Provide 1-in. bars at 7-in. centres.

#### London Telecommunications Centre.

THE Fleet Building (Fig. 1) in Farringdon Street is the new telecommunications centre for London and has been built for the General Post Office to accommodate equipment and office staff. The building, which is of reinforced concrete construction, has fifteen floors and is approximately 165 ft. high above street level. The plan of the building, which is governed by operational requirements and the location of apparatus, is based on a module dimension of 11 ft. 51 in. in both directions. The site has frontages of 230 ft., 250 ft., and 230 ft. on streets on three sides; the remaining boundary adjoins existing buildings. The building is founded on firm clay at a depth of up to 50 ft. below the pavement. The basement walls (Fig. 2) are of semi-mass concrete, lightly reinforced, with a maximum thickness of 9 ft. Most of the retaining walls were constructed by the trench-and-dumpling method. Little water was encountered during excavation

and the concrete walls in contact with the clay have no watertight membrane.

In most cases the columns are supported on the retaining walls or on the foundation raft, but bored piles are provided on the northern part of the site due to the proximity of existing buildings. The spacing of the external columns is 5 ft. 84 in. In operational areas, the beams are at 5-ft. 81-in. centres. Generally columns and beams are not plastered. Column and pier sizes were standardized. The lower six floors comprise solid-slabs designed to carry heavy loads from the equipment; the storey height is 14 ft. 9 in. The remaining nine floors are to ft. from floor to floor and of hollow clay-block construction designed for office loading. The roof is of similar construction. Where hollow-block construction is used the soffit is flush between the internal spine beam and external columns. On the northern side there are three stairs of various widths; one stair projects to serve



Fig. 1.



Fig. 2.

as a "stop" to the northern elevation and as a support to the adjoining party-wall.

Drainage in the ground-floor kitchen area is accommodated within a space I ft. 3 in. deep between the solid floor slab and the underside of the false ceiling to the basement. The space is watertight to protect the apparatus immediately below. Plumbing and sanitary services are generally in two vertical ducts which extend throughout the height of the building. To enable the "Telex" equipment to be installed at an early date, temporary overhead protection was provided in the basement while construction of the superstructure proceeded.

The external finish is Portland stone with the exception of end flank walls, which are finished with Derbydene stone. A number of ceramic faience murals, depicting Post Office activities, have been erected to the right of the main entrance.

The building, the estimated cost of which is about £1,900,000 and which has a volume of about £1,20,000 cu. ft., was designed by the Architect's Department of the Ministry of Works. The Structural Department of the Ministry worked in conjunction with Messrs. W. V. Zinn and Associates. The general contractors were Messrs. Tersons Ltd.

#### Analysis of Frames with V-supports.

In Fig. 5 of the article entitled "Analysis of Frames with V-supports", in the number of this journal for April 1961, the bending-moment diagrams for members 2-A and 5-B should be drawn on the other side of the member to that shown, since the diagrams are on the "tension side" of each member.

#### A Concrete Ship.

A 3500-ton ship, which is being built of reinforced concrete at a Baltic shipyard, will be about 280 ft. long, with a beam of 55 ft., and is due for completion this autumn. This ship, which is a refrigerated vessel, will be used for the storage of fish and the production of ice for a fishing fleet.

## A Practical Comprehensive Method of Designing Reinforced Concrete Sections.—II.\*

By J. RYGOL, B.Sc.(Eng.).

#### ELASTIC (MODULAR-RATIO) METHOD.

THE assumed triangular distributions of stresses and strains are shown in Fig. 7.

#### Basic Equations and Factors.

**Basic Equations.**—The basic equations (1), (2) and (3) in Part I, expressed in terms of the tensile stress  $f_{\theta}$  are

$$N = K_s \frac{f_s}{m} bd \qquad . \qquad . \qquad . \qquad . \tag{1a}$$

$$M_t = Ne_t = S_t \frac{f_s}{m} b d^2 \qquad . \qquad . \qquad . \qquad (2a)$$

$$M_{\epsilon} = Ne_{\epsilon} = S_{\epsilon} \frac{f_{\epsilon}}{m} b d^2$$
 . . . (3a)

where  $K_s$ ,  $S_t$ , and  $S_c$  are the stress factors for  $f_s$ , and  $K_s = \frac{S_t - S_c}{I - \beta'}$ .

**Shape Factors.**—The stress-block factors  $\kappa_1$ ,  $\kappa_2$  and  $\kappa_3$  may be expressed in





Fig. 7.

\* Continued from June, 1961.



Nomogram No. 1.

the form  $\kappa_1 = \frac{\phi_1}{\kappa_1}$ ,  $\kappa_2 = \frac{\phi_2}{\kappa_2}$  and  $\kappa_3 = \frac{\phi_3}{\kappa_3}$ , where  $\phi_1$ ,  $\phi_2$  and  $\phi_3$  are dependent on the shape of the compression zone only and are termed the shape factors.

Stress-factor Equations.—The stress factors may be expressed directly in terms of the shape factors and modular and reinforcement ratios thus.

$$K_c = \frac{\phi_1 + (n - \beta')(m - 1)\phi' - (1 - n)m\phi}{n}$$
 . (13)

$$C_{i} = \frac{\phi_{3} + (n - \beta')(1 - \beta')(m - 1)\beta'}{n} \qquad . \tag{14}$$

$$C_c = \frac{-\phi_3 + (\mathbf{1} - n)(\mathbf{1} - \beta')mp}{n} \qquad . \tag{15}$$

$$K_s = \frac{\phi_1 + (n - \beta')(m - 1)\beta' - (1 - n)m\beta}{1 - n}$$
 . (16)

$$S_{i} = \frac{\phi_{3} + (n - \beta')(1 - \beta')(m - 1)\beta'}{1 - n} \qquad (17)$$

$$S_c = \frac{-\phi_3 + (\mathbf{I} - n)(\mathbf{I} - \beta')mp}{\mathbf{I} - n} . . . . (18)$$

Simple Bending.—For simple bending  $K_c = K_s = 0$ ,  $C_t = C_o = C$  and  $S_t = S_c = S$ ; therefore  $\phi_1 + (n - \beta')(m - 1)p'_b - (1 - n)mp_b = 0$ .

It should be noted that the moment of inertia I of the transformed concrete section can be expressed as  $\mu b d^3$ , where  $\mu = Cn = S(1 - n)$ .

Section with Tension Reinforcement Only.—Since (m-1)p'=0,

$$R_c = \frac{\phi_1}{n} - \frac{(\mathbf{r} - \mathbf{n})}{n} \bar{m} \bar{p} \qquad . \qquad . \qquad . \qquad . \qquad . \tag{13a}$$

$$C_t = \frac{\phi_s}{\sigma_t}$$
 . . . . . . . . (14a)


$$\hat{R}_s = \frac{\phi_1}{(1-n)} - \hat{m}\bar{p} \quad . \quad . \quad . \quad (16a)$$

$$S_t = \frac{\phi_2}{(r-n)} \quad . \quad . \quad . \quad . \quad . \quad (17a)$$

Section with Tension and Compression Reinforcement.—The relationships derived in Part I may be expressed as follows.

where 
$$\begin{split} mp &= \bar{m}\bar{p}_b + \Delta mp - K_s \\ S_t &= \bar{S}_t + \Delta S_t \\ M_t &= \bar{M}_t + \Delta M_t \\ \text{where} \quad \Delta mp &= \frac{(n-\beta')}{(\mathbf{x}-n)}(m-\mathbf{x})p' \text{ and } \bar{m}\bar{p}_b = \frac{\phi_1}{(\mathbf{x}-n)}, \\ \Delta S_t &= \frac{(n-\beta')(\mathbf{x}-\beta')}{(\mathbf{x}-n)}(m-\mathbf{x})p' \end{split}$$

and 
$$\Delta M_t = \Delta S \frac{f_s}{m} b d^2$$
.



Nomogram No. 2.

#### Application of Method.

The examples which follow illustrate the application of the method. Nomograms are given to enable the calculations to be made quickly and easily.

Nomograms Nos. 1 and 2 apply to a general trapezoidal section, particular cases of which are a triangular section ( $\gamma = 0$ ) and a rectangular section ( $\gamma = 1$ ). The equations on which these nomograms are based are as follows.

Nomogram No. 1 (page 248).— 
$$\bar{m}\bar{p}_b = \frac{n^3}{6(1-n)} + \gamma \frac{n^2(3-n)}{6(1-n)}$$
  
Nomogram No. 2 (page 250).—  $S_t = \frac{n^2(2-n)}{12(1-n)} + \gamma \frac{n^2(6-4n+n^2)}{12(1-n)}$ 

The shape of a trapezoidal section (Fig. 8a) is described by the ratio  $\gamma = b_o/b$ , where  $b_o$  is the breadth of the section at the extreme compression edge and b is the breadth of the section at the centroid of the tension reinforcement. Sections such as those in Figs. 8(b) and (c) can be treated as trapezoidal if the neutral axis falls within the inclined sides of the section; b is obtained by projecting the inclined sides down to the centroid of the tension reinforcement.

As rectangular sections occur frequently, other nomograms, enabling solutions for such sections, when, reinforced in tension and compression, to be obtained even more rapidly and simply than by using Nomograms Nos. 1 and 2, have been prepared and will be included in Part III.

A design is either a balanced design, in which the position of the neutral axis  $= n_o$  and is based on the permissible stresses being attained simultaneously, or is controlled by the resistance of the tension reinforcement, in which case  $n < n_o$ , or the resistance of the concrete in compression, in which case  $n > n_o$ .

#### Examples of Use of Nomograms Nos. 1 and 2.

Example No. 1. Given. — Trapezoidal section. b = 12 in.  $b_0 = 18$  in.




Fig. 8

252

d = 27 in. M = 2,000,000 in.-lb. Permissible  $f_c = 1100$  lb. per sq. in.  $f_b = 20,000$  lb. per sq. in. m = 15.

To determine.— $A_{\bullet}$  (and  $A_{\bullet}$  if required), and actual stress in concrete (or reinforcement).

Solution.—
$$\gamma = \frac{b_0}{b} = \frac{18}{12} = 1.5, \quad n_0 = 0.452.$$

$$S_1 = \frac{2,000,000}{\frac{20,000}{15} \times 12 \times 27^2} = 0.171.$$

From Nomogram No. 2 (with y = 1.5,  $S_t$ , = 0.171), n = 0.404, and as this is less than  $n_0 = 0.452$ , compression reinforcement is not required.

From Nomogram No. 1 (with y = 1.5, n = 0.404),  $\tilde{m}b_b = 0.198$ ; hence

$$A_s = \frac{0.198}{15} \times 12 \times 27 = 4.28 \text{ sq. in.}$$

$$f_c = \left(\frac{n}{1-n}\right) f_c = \frac{0.404}{1-0.404} \times \frac{20,000}{15} = 904 \text{ lb. per sq. in.}$$

Example No. 2. Given. — Rectangular section. h=30 in. b=18 in. g=g'=2 in. N=80,000 lb. (compressive). s=35 in. Permissible  $f_c=1200$  lb. per sq. in.  $f_s = 20,000$  lb. per sq. in. m = 15; hence  $n_0 = 0.473$ . To determine.— $A_s$  (and  $A_s$ ' if required).

Solution.—
$$d = 30 - 2 = 28$$
 in.;  $\beta = \beta' = \frac{2}{28} = 0.07$ .  
 $e_t = 35 + \frac{30}{2} - 2 = 48$  in.;  $e_c = 35 - \frac{30}{2} + 2 = 22$  in.

 $M_t = 80,000 \times 48 = 3,840,000 \text{ in.-lb.}; \quad M_t = 80,000 \times 22 = 1,760,000 \text{ in.-lb.}$ 

$$S_t = \frac{3,840,000}{\frac{20,000}{15} \times 18 \times 28^3} = 0.204.$$

From Nomogram No. 2 (with  $\gamma = 1$ , n = 0.473),  $\bar{S}_t = 0.179$ . Since  $S_t > \bar{S}_t$ , compression reinforcement is required;  $dS_t = 0.204 - 0.179 = 0.025$ . From Nomogram No. 1 (with  $\gamma = 1$ , n = 0.473),  $\tilde{m}\tilde{p}_b = 0.213$ 

$$Amp = \frac{0.025}{1 - 0.07} = 0.027$$

$$-K_s = \frac{-80,000}{\frac{20,000}{15} \times 18 \times 28} = -0.119$$

$$mp = 0.121$$

$$(m - 1)p' = \frac{1 - 0.473}{0.473 - 0.07} \times 0.027 = 0.035.$$

$$A_s = \frac{0.121}{15} \times 18 \times 28 = 4.07 \text{ sq. in.}$$

$$A_s' = \frac{0.035}{14} \times 18 \times 28 = 1.26 \text{ sq. in.}$$

Example No. 3. Given. — Trapezoidal section. d=22 in. b=15 in. M=920,000 in.-lb. Permissible  $f_c=1000$  lb. per sq. in.  $f_b=18,000$  lb. per sq. in. m = 15; hence  $n_0 = 0.455$ .

#### DESIGNING REINFORCED CONCRETE SECTIONS-11.

To determine.—
$$b_0$$
 and  $A_4$ .

Solution.—
$$S_t = \frac{920,000}{\frac{18,000}{15} \times 15 \times 22^3} = 0.106$$

From Nomogram No. 2 (with  $S_t = 0.106$ ,  $n = 0.106$ )

From Nomogram No. 2 (with  $S_t = 0.106$ , n = 0.455),  $\gamma = 0.60$ , therefore  $b_0 = \gamma b = 0.60 \times 15 = 9 \text{ in.}$ 

From Nomogram No. 1 (with y = 0.60, n = 0.455),  $\tilde{m}\tilde{p}_{\theta} = 0.127$ , hence

$$A_8 = \frac{0.127}{15} \times 15 \times 22 = 2.79$$
 sq. in.

EXAMPLE No. 4. Given. — Trapezoidal section. d = 14 in.  $b_{\theta} = 9$  in.  $A_{\theta} = 1.23$  sq. in.  $A_{\theta}' = 0$ . m = 15. M = 250,000 in.-lb. To determine.— $f_0$  and  $f_c$ .

Solution. 
$$-\gamma = \frac{b_0}{b} = \frac{9}{12} = 0.75$$
.  $\bar{m}\tilde{p}_b = \frac{15 \times 1.23}{12 \times 14} = 0.110$ .

From Nomogram No. 1 (with  $\gamma = 0.75$ ,  $\tilde{m}\tilde{p}_b = 0.110$ ), n = 0.405. From Nomogram No. 2 (with  $\gamma = 0.75$ , n = 0.405),  $S_4 = 0.094$ .

$$f_s = 15 \times \frac{250,000}{0.094 \times 12 \times 14^2} = 16,960 \text{ lb. per sq. in.}$$

$$f_c = \frac{0.405}{1 - 0.405} \times \frac{16,960}{15} = 770 \text{ lb. per sq. in.}$$

Given. — Trapezoidal section. b = 12 in.  $b_0 = 21$  in. EXAMPLE No. 5. g'=3 in. N=100,000 lb. (compressive). e=25 in. Permissible  $f_0=1000$  lb. per sq. in.  $f_0 = 20,000$  lb. per sq. in. m = 15; hence  $n_0 = 0.429$ .  $A_0' = 0$ .

To determine.-d and As. Solution.  $-\gamma = \frac{21}{13} = 1.75$ .

From Nomogram No. 2 (with  $\gamma = 1.75$ , n = 0.429),  $S_1 = 0.228$ . The required effective depth, d, can be determined from equation (2a) rewritten in the the form  $N(e + \frac{d - g'}{2}) = S_t \frac{f_s}{m} b d^2$ ,

that is 100,000  $\times \left(25 + \frac{d-3}{2}\right) = 0.228 \times \frac{20,000}{15} \times 12 \times d^2$  from which d = 33 in.

From Nomogram No. 1 (with  $\gamma = 1.75$ , n = 0.429),  $\tilde{m}\tilde{p}_b = 0.268$ 

$$-K_{\theta} = \frac{-100,000}{\frac{20,000}{16} \times 12 \times 33} = -0.189$$

$$A_8 = \frac{0.079}{15} \times 12 \times 33 = 2.09$$
 sq. in.

Given. — Triangular section. d = 14 in. b = 18 in. EXAMPLE No. 6. N=7000 lb. (tensile).  $e_t=7$  in. Permissible  $f_c=880$  lb. per sq. in.  $f_a=16,000$  lb. per sq. in. m=12; hence  $n_0=0.398$ .

To determine.— $A_a$  (and  $A_a$ ' if required).

Solution.-

$$S_4 = \frac{7000 \times 7}{\frac{16,000}{12} \times 18 \times 14^2} = 0.0104.$$

From Nomogram No. 2 (with y = 0,  $S_4 = 0.0104$ ), n = 0.365. As  $n < n_0$  therefore compression reinforcement is not required.

July, 1961.

From Nomogram No. 1 (with y = 0, n = 0.365),  $\tilde{m}\tilde{p}_0 = 0.0127$ 

$$-K_s = -\frac{-7000}{\frac{16,000 \times 18 \times 14}{12}} = 0.0208$$

$$\bar{m}\bar{p} = 0.0335$$

$$A_4 = \frac{0.0335}{12} \times 18 \times 14 = 0.704$$
 sq. in.

$$f_e = \frac{0.365}{1 - 0.365} \times \frac{16,000}{12} = 766$$
 lb. per sq. in.

Example No. 7. Given. — Rectangular section. b=12 in. g=1.75 in. N=14,000 lb. (compressive). e=22 in. Permissible  $f_e=1000$  lb. per sq. in.  $f_8 = 20,000$  lb. per sq. in. m = 15; hence  $n_0 = 0.429$ .  $A_8' = 0$ .

To determine. -d and As. Solution.—Assume  $\beta' = 0.14$ . From Nomogram No. 1 (with  $\gamma = 1$ , n = 0.429),  $m\bar{p}_0 = 0.161$ . From Nomogram No. 2 (with  $\gamma = 1$ , n = 0.429),  $S_t = 0.138$ . The eccentricity factor is given by  $U_t = \frac{N}{\frac{f_0 cb}{m}} = \frac{14,000}{20,000} = 0.398$ ,

eccentricity factor is given by 
$$U_s = \frac{N}{\frac{f_s e b}{m}} = \frac{14,000}{\frac{20,000}{15} \times 12 \times 22} = 0.398,$$

d can be determined from the equation  $\epsilon_0 \left( \epsilon_0 + \frac{1 - \beta'}{2} \right) = \frac{S_t}{U}$ , that is

$$\varepsilon_0(\varepsilon_0 + 0.43) = \frac{0.138}{0.0398} = 3.46,$$

from which  $\varepsilon_{\theta} = 1.66$  and therefore  $d = \frac{e}{\varepsilon_0} = \frac{22}{1.66} = 13.25$  in.

Checking assumed value of  $\beta$ —  $\beta = \frac{1.75}{13.25} = 0.13$  which is about the value assumed.

assumed. 
$$R_s = \frac{14,000}{\frac{20,000}{15} \times 12 \times 13.25} = 0.066, \quad \tilde{m}\tilde{p} = \tilde{m}\tilde{p}_b - \tilde{R}_s = 0.161 - 0.066 = 0.095.$$

$$A_8 = \frac{0.095}{15} \times 12 \times 13.25 = 1.01 \text{ sq. in.}$$

Example No. 8. Given. — Rectangular section. g = 1.5 in. N = 6300 lb. (tensile),  $\sigma = 47$  in. Permissible  $f_c = 900$  lb. per sq. in.  $f_b = 20,000$  lb. per sq. in. m = 15; hence  $n_0 = 0.403$ .  $m\bar{p} = 0.175$ .  $A_s' = 0$ .

To determine. -d and b.

Solution.—From Nomogram No. 1 (with  $\gamma=1, n=0.403$ ),  $\tilde{m}\tilde{p}_b=0.136$ . From Nomogram No. 2 (with  $\gamma=1, n=0.403$ ),  $S_t=0.118$ .

$$\vec{R}_s = \vec{m}\hat{p}_b - \vec{m}\hat{p} = 0.136 - 0.175 = -0.039.$$
  $s = \frac{S_t}{R_s} = \frac{0.118}{0.039} = 3.026.$ 

Assuming  $\beta = 0.10$ ,  $\varepsilon_0 = \varepsilon + \frac{1-\beta}{2} = 3.026 + \frac{1-0.10}{2} = 3.476$ , and therefore

$$d = \frac{e}{e_0} = \frac{47}{3.476} = 13.52$$
 in., say 13.5 in.

Checking assumed value of  $\beta$ .—  $\beta = 1.5/13.5 = 0.11$  which is about equal to the value assumed.

$$b = \frac{Ne_t}{S_t \frac{f_a}{m} d^2} = \frac{6300 \times (47 - 6)}{0.118 \times \frac{20,000}{15} \times 13.5^2} = 9.0 \text{ in.}$$

(To be continued.)

### Developments in the Ready-mixed Concrete Industry.

Interesting features of some readymixed concrete plants installed recently in Britain and of other activities in this branch of the concrete industry are described in the following.

#### A Plant in West Kent.

The plant illustrated in Fig. 1 has a rated capacity of 30 cu. yd. of concrete per hour. The aggregate is dredged from the bed of a lake and delivered to a washing, crushing, and screening plant, from which sand and various sizes of coarse aggregate are delivered by an inclined belt-conveyor to stockpiles located between the screening and concrete plants. The conveyor and some of the stockpiles are seen to the left in Fig. 1. Under the stockpiles, there is a concrete conveyor tunnel (Fig. 2), 274 ft. long, 5 ft. 6 in. wide and 6 ft. 6 in. high, in the roof of which there are thirteen hoppers through which the flow of materials from the stockpiles on to the belt-conveyor in the tunnel is controlled. The gate of a hopper in the closed position is shown in Fig. 2. The conveyor is 24 in. wide and travels at a speed of 300 ft. a minute. The gates are controlled from the cabin seen in Fig. 3. The levers operate stranded-wire cables, each of which is attached to a gate which opens when the lever is pulled forward. When the lever is released, the gate closes by means of a counterbalance.

At the exit from the tunnel, the conveyor rises at an angle of 25 deg., and delivers the material to a transverse conveyor (Fig. 4), which is suspended from a steel beam and tranverses four bins each of which is for an aggregate of a different size. The movement of the conveyor over the bins is controlled by the operator in the cabin (Fig. 3). The bins, each of which has a capacity of 71 cu. yd., are over a pit into which descends the skip which delivers the materials to the elevated mixer (Fig. 5). The capacity of the skip is sufficient for the materials for I cu. yd. of concrete. The cement is stored in the two silos seen to the right in Fig. 5; one silo is for ordinary Portland




Fig. 1.-Plant near Sevenoaks.

cement and the other for rapid-hardening Portland cement; each silo has a capacity of 30 tons.

The operation of the mixing plant is semi-automatic. The material is weighbatched by manual controls actuating the doors of the bins. The cement is transferred by air-slides from the silos to the weigh-batcher and is delivered by an electro-pneumatic system operated by a push-button from the control panel alongside the operator's seat (Fig. 6). Weighing is by sealed hydraulic capsule. All materials are weighed together, including the cement, as a total weight on the dial of the scale. The quantity of water required for each batch is set on a flowmeter by the operator. The contents of the weigh-batcher are emptied by pneumatic control into an elevating skip, and then a button is pressed to operate the hoisting mechanism of the skip, which discharges its contents into the mixer. At the same time the water-meter operates automatically, and the required quantity of water flows into the mixer. The mixer is a 1-cu. yd. horizontal-drum machine. When mixing is complete, a push-button is operated to cause the discharge of the concrete into a hopper, from which it is delivered along a chute to cone-shaped agitator drums on a lorry.

The aggregate plant is also used for supplying aggregates, either of mixed sizes or of one size, to destinations other than the ready-mixed concrete plant. In this case the transverse conveyor is not



Fig. 2.

used since the material is delivered from the end of the main conveyor directly into lorries.

Two men are employed on the plant, one controlling the supply of aggregate to the bins over the mixer and one operating the mixing plant. The plant is operated by Messrs. Redland Quarries, Ltd., at Riverhead, Kent, which firm designed



Fig. 3.

## The £.s.d of OSAL\* - Surface waterproofing of Brick. Concrete and Stone.

but the cost per gallon the cost per yard that counts

Using Neocosal, a 1\(\frac{1}{4}d\), per square foot is all that it costs effectively to provide surface waterproofing of Brick, Concrete and Stone. Neocosal, a colourless liquid water repellent, penetrates the surface, forming an effective water seal.

#### SILICONE



Leading Architects have been specifying Neocosal for 30 years or more, for its economy, efficiency and because it does not discolour surfaces. Send for information Leaflet No. 3.

\* Osal is the generic name for the products of A. A. BYRD & CO. LTD.—Florosal, Neocosal, Tricosal and Lubrosal. Literature about each individual product is available on request.

A. A. BYRD & CO. LTD. (Dept CB) 210 TERMINAL HOUSE, GROSVEHOR GARDENS, LONDON, S.W.1
Phone: SLOane 5236

Grams: Byrdicom, Wesphone, London 'Works: Basingstoke, Hants



FORMWORKS
AND MOULDS
N USE OVERSEAS

THE
WORLD-WIDE
USE OF



#### STELMO FORMWORKS AND MOULDS

in the countries listed below well illustrates the unique international experience of the STELMO SERVICE in catering for the design and supply of steel formworks and moulds for all insitu and precast concrete requirements.

ADEN
AUSTRALIA
CAMADA
CEYLON
CUBA
DOMINICAN REPUBLIC
GHANA
GUIANA

HONG KONG INDIA IRAQ JAMAICA KENYA LEBANON MAURITIUS

NIGERIA

**NEW ZEALAND** 

PAKISTAN SIERRA LEONE SOUTH AFRICA SUDAN SUMATRA TANGANYIKA TIMOR TRINIDAD

Wherever your contract or precast works are situated, remember that the STELMO SERVICE will give you the best results with the longest-term economies.

CONSULT US NOW!



the most comprehensive mould service in the world

STELMO LTD · WESTWELL LEACON · CHARING · ASHFORD · KENT Tel: Charing 395-6-7



Fig. 4.

the arrangements for the transport and delivery of the aggregates and installed the whole of the plant.

#### A Plant in East Kent.

The plant illustrated in Fig. 7 was installed recently at Chilmington, near Ashford, and incorporates a new design of 1-cu. yd. pan-type mixer having a rated output of 60 cu. yd. per hour. The low-level batcher has storage capacity for 30 cu. yd. of aggregates in four compartments and is loaded from the stockpiles by a mobile tractor-shovel. The aggregate-weigher is of 42 cu. ft. capacity and weighing accuracy is assured by a patented hydraulic system. The feed-

gates and discharge gates of the weigh hopper are electro-pneumatically operated by remote control from a main control panel near the mixer in the tower. The weigher discharges dry aggregates on to a troughed belt-conveyor which carries them to the mixer.

Two 30-ton cement silos are provided for the separate storage of ordinary and rapid-hardening Portland cement. The capacity of the storage of cement can be increased by connecting up additional silos by means of fluidising conveyors. The cement is weighed, independently of the aggregates, in a 800-lb. weighing apparatus. The cement silos being elevated, permit the cement to be discharged




Fig. 5.-Plant near Sevenoaks.




Fig. 6.

from the weigher directly into the pan of the mixer thereby obviating prior contamination of the cement by any moisture in the aggregates. Accurate measure-ment of the water is achieved by a flowmeter control. The mixer is mounted on an elevated platform thereby enabling it to discharge directly through a new type of swivelling telescopic discharge chute into agitators, mobile mixers or lorries.

The plant at Chilmington is operated by Nickolls Ready-mixed Concrete Co., Ltd. The batching and mixing equipment

and the cement silos for the plants at



Fig. 7.-Plant near Ashford.

# SULPHATE-LADEN SOILS

To eliminate risk
CIMENT FONDU
SHOULD BE USED

To ensure complete protection CIMENT FONDU MUST BE USED

made with
CIMENT FONDU is
COMPLETELY IMMUNE
from the effects of
SULPHATES
in any concentration

Concrete

Concrete made with Ciment Fondu provides an additional margin of safety! It is also resistant to attack by dilute acids often prevalent in sulphate-bearing clays, made-up ground and many industrial effluents.



\* Send for leaflet TSS-16" The Influence of Mineral Sulphates on the Permanence of Conerose Structures."

LAFARGE ALUMINOUS CEMENT COMPANY LTD., 73 Brook St., London, W.1. Tel: MAY 8548





### Experts agree on their...

#### **ADVANCED DESIGN**

CCL Spiral Anchorages for both wire and strand are the most advanced and reliable anchorages you can obtain. Made by the world's largest manufacturer of mechanical anchorages they are backed by a responsible organisation, which is anxious to be of service to you.

#### FREE

24 page booklet of technical data and site information sheets on the CCL Prestressing systems



WRITE NOW TO:

CABLE GOVERS LIMITED St Stephen's House (Technical Service Dept) Westminster S.W.1

Riverhead and Chilmington were supplied by Blaw Know Ltd.

#### A Plant in Essex.

A ready-mixed concrete plant, which was installed recently at the new town of Harlow, Essex, is one of a number of purposed-designed plants planned to take advantage of irregularities in the levels of the sites at which the plants are to be erected. The advantage is mainly the omission of major types of equipment for

handling materials.

In the plant at Harlow, an elevated bin for aggregate, having a capacity of 80 cu. yd., has four compartments and is mounted immediately over the batch weigh-hopper. The materials are tipped directly into the bin from lorries which approach the plant on a gantry extending from adjacent high ground. Open-mesh steel wheel-tracks span the bin to enable materials to be discharged into the compartments on the far side of the structure.

A 40-ton cement silo is provided on the side of the plant remote from the gantry. Cement is fed into the silo from pressurised tankers standing on a road at the lower ground level. A static bag-filter surmounts the silo to prevent building up

of pressure during filling.

The weigh-hopper, which contains sufficient material for 4 cu. yd. of concrete,

has two compartments.

The plant was designed and is owned by Ready Mixed Concrete (Eastern Counties) Ltd., in association with Messrs. Peters & Barham Ltd.

#### A Plant in Cheshire.

The concrete batching and mixing plant installed at the Sealand Trading Estate, Cheshire, is completely automatically controlled by one operator, at a pushbutton console, and is capable of producing 60 cu. yd. of ready-mixed concrete per hour. The aggregate storage hopper, having a total capacity of 48 cu. yd., is divided into four equal compartments, each having a twin outlet fitted with radial gates operated pneumatically by 4-in. cylinders. Beneath the hopper, and supported on the same structure, is an aggregate weigh-hopper carried in a precision batch-weigher. The weighing system is connected to a dial mounted on the operator's platform.

A twin-compartment, 30-ton cement silo is equipped with a pneumatic conveyor and blowing unit for delivery to a surge hopper of 10 tons capacity and having two compartments, each of which is fitted with a ventilator filter at the top. Supported on the same structure and beneath the surge hopper, there is a cement weigh-hopper which is also connected to a dial on the operator's platform. The weigher outlet is fitted with reverse radial gates operated pneumatic-

ally by 3-in. cylinders.

Before commencing production, the operator adjusts transistorised photoelectric scanning heads to give the required weight of aggregate and cement from each storage hopper. To begin production, the operator presses a "start" button for weighing aggregate and cement simultaneously. The respective doors open, and the materials discharge into the weigh hoppers; the doors close automatically when the predetermined quantity has been delivered. The action of the weightrecording pointer passing the photo-cells on the dial settings causes electrical impulses to pass to solenoid valves which in turn operate the cylinders. The aggregate doors continue to open and close in succession and lights on the control platform indicate when the weighing of both materials is complete. This part of the cycle being complete, the operator pre-sets the "unload for mixing" button and the aggregate is discharged on to an inclined belt-conveyor, which is 84 ft. long and discharges into a 11-cu. yd. paddlemixer. A time-delay apparatus ensures that the cement and aggregate discharge into the mixer simultaneously. Water is added by the operator, the amount being pre-set on a water-meter; a 3-in. pneumatic cylinder operates the valve controlling the flow of water. The opening of the valve is controlled by the operator but the closing is automatic on receipt of a signal from the water-meter.

In addition to the automatic controls, the operator has manual controls enabling him to weight directly. Electro-pneumatic control is also provided in the cement conveyor system to divert the flow of cement to one or other of the silos when being filled from the blowing unit. The adjustable chute beneath the mixer is designed to discharge into mobile mixers

or open lorries.

The mixing plant, control console, switchgear and the vehicle loading position are totally enclosed in a housing of steel frame and asbestos sheeting. The fact that this plant is operating at a city boundary raised problems of height, appearance, noise and dust. By installing the aggregate weigh-hopper and elevator below ground level, the overall height of the aggregate storage unit was reduced. Pneumatic control, the provision of rubber and canvas conveyor belts with ball-bearing rollers, and the quiet-running paddle-mixer combine to reduce noise to a minimum.

The plant was designed and manufactured by Millar's Machinery Co., Ltd., and is owned by John Henshall (Quarries) Ltd.

#### A Record Supply.

In connection with the foundations of the new Hilton hotel being erected in Park Lane, London, 1185 cu, yd. of ready-mixed concrete was delivered and placed in a period of twelve hours. To achieve this quantity without interrupting supplies to other contracts, the suppliers combined the outputs of three plants in the London area. Delivery was made in transit mixers of capacities varying from 3 to 6 cu, yd. Supplies arrived at the site at intervals of 21 minutes.

The transit mixers stood on the road 60 ft. above the foundation being constructed and discharged the concrete through extension chutes fitted to the vehicles into flexible metal trunking through which the concrete was fed to the lower level of the site. To assist in transporting the concrete to the central area of the foundation, the concrete was discharged from the trunking into hoppers from which it was discharged on to two belt-conveyors. Each vehicle was despatched from the site within five minutes of its arrival.


The contractors are the Token Construction Co., Ltd., and the concrete was supplied by the Ready Mixed Concrete Co., Ltd.

#### Bulletin Received.

"Preconditioning and Stabilizing Soils by Lime Admixtures." Bulletin No. 262. Highway Research Board. (1960. Price 1.80 dollars.)

# Patent Applications for Curing Concrete.

APPARATUS for curing concrete test specimens 8 comprises a cabinet 1, a water reservoir 2 and a pump 5 which circulates water in the cabinet via spray nozzles 7 to maintain a predetermined level of humidity which is usually 90%. The specimens are heated by an electric heater,



the temperature being maintained between 60° F.—80° F. by a thermostat while a limit switch, Fig. 3 (not shown), is arranged to cut off the water pump 5 when the cabinet door 11 is opened. A humidity meter regulating the output of the water pump may also be fitted.—No. 845,380. Simon-Carves Ltd. December 30, 1958.

Concrete is cured by spraying thereon a membrane-forming composition in which is dispersed aluminium in leaf or powder form protected against chemical attack by alkaline salts in the fresh concrete. Protective agents specified are metal soaps such as calcium and zinc stearates; these also assist in dispersing the aluminium in the composition. Organic solvents in a proportion of e.g. 2 to 4 per cent. by weight, such as carbon tetrachloride, trichloroethylene or petroleum solven s obtained by distillation, may be added to facilitate mixing the aluminium with the composition. In examples are described membrane-forming compositions consisting of aluminium paste, carbon tetrachloride or white spirit, calcium or zinc stearate, and a curing composition having the Registered Trade Mark "Ritecure' Proportions of aluminium paste and metallic soap are 2 to 4 per cent., and up to 4 per cent., respectively.-No. 846,885. J. Laing & Son Ltd. August 7, 1956.

# After you, the person who knows most about your concrete is the **POZZOLITH** field man.



# This technician – backed by facilities like this mobile laboratory, brings to your site an unequalled product and a unique service.

Additives have contributed to the building of many magnificent concrete structures, but only too often they are not intelligently applied and do not give the intended results.

So that you might see the role of additives in true perspective, Pozzolith—the world's leading water reducing admixture, invented as far back as 1932—has recently been introduced to this country. You now have the opportunity to see and appreciate

the values of this concrete control; demonstrated and explained by men who know what concrete will and will not do. Behind them is a research unit unmatched in this field. And on every project on which the Pozzolith method is used, engineers will be on hand to provide unique, on-the-spot technical assistance. This is just one of the ways in which Pozzolith is awakening new interest in this vital subject.

Write for further details to

Manufactured and distriluded in Great Britain by MILL AR's MA CHINERY COMPANY LIMITED Process Hall, Great Winchester Breen, Licelen, E.C.2.

POZZOLITH

Millars

Under licence from YHE MASTER BUILDERS' CO. A division of American Marietta Company. STRUCTURE-3 STOREYS-228 FRONTAGE

PINISHED

The structure illustrated indicates just one of the services offered by the Modular Concrete Co. Ltd.

A prefabricated building on a 12' × 12' column grid with a 6' corridor between. Plan form and height variable.

It consists of TWO
components:—
S. subsesses seet is
see length
15' x 11' floor slabs
integrated perimeter

Columns contain fabricated steel alear connectors on to which the floor alabs seat directly without propping. The neethed makes for extremely quick and safe erection procedure and efficients of procedure and efficients of procedure and efficients of procedure and efficients of connection of precast elements.

-0-21-

-12.0°

connection of precast elements
All services can be catered for
quite simply.
Speed and economy result

ERECTED BY

FLOOR PANEL

PRECAST COLUMN

0 × 6

11-0

Speed and economy result from SIMPLICITY AND REPETITION—strated by this example of OFTIMUM PREFARRICATION.

48 DAYS

Write or 'phone Modular

Modular Com

# THE MODULAR CONCRETE COMPANY LIMITED

Construction Division, 1280 London Road, Nurbury S.W.16

TELEPHONE: POLLA RDS 8000

#### Failures of Foundations.

An interesting and informative book\* on the unusual subject of failures of foundations was published recently. Numerous examples of defective foundations and defective structures due to failure of foundations, in many parts of the world, are described and examined. The causes and prevention of like failures are discussed. Of particular interest are the examples drawn from Central Europe, details of many of which have not been available before. Other well-known failures are re-examined.

The author is Professor of Foundation Engineering at the University of Civil Engineering and Architecture at Budapest, and is the author of a similar book published in Hungary. In the present publication there are, however, very many additional examples including some from Great Britain. Although the soil-mechanics aspect of the subject is given due prominence, there is a commendable absence of mathematics and there is much common sense.

Some opinions of the book are given in the following.

Mr. G. P. Manning writes as follows.

When the Foundations Code No. 4 was being drafted I suggested that British engineers should collect and publish details of their foundation failures. The horrified silence that ensued is still unbroken. Therefore the publication of this book is a most notable addition to our technical literature and is worthy of the attention of every practising civil engineer.

It is difficult to criticise any structural design without knowing something of the background, including the economic conditions and national outlook. Several of the foundations described are deliberately placed on new earth filling where, in Great Britain, we should invariably use mass concrete in place of filling. The saving in cost would be trivial in this country, and the use of gravel filling instead of lean concrete indicates the need for saving in first cost. Accepting this premise as the first and over-riding necessity, the examples and the remedies suggested by the

author appear much more rational than they would otherwise seem. Although the reader may occasionally disagree with the author's explanations they are clearly the result of much thought and always worth careful consideration.

Mr. Leslie Turner writes as follows.

The author and publishers are to be congratulated on the production of this book. The illustrations and charts are in English and all dimensions have been converted into English units. The subject is vast, combining an understanding of geology, soil mechanics and structural design, aspects of all of which must be considered together. Each example is unique, as it must be in practice and rarely recurs in detail although the underlying correlations are obvious and must be absorbed by all qualified structural designers.

In the design of column footings on clay, more stress should be laid on designing for equal settlement rather than for uniform ground pressure. This is the requisite for perfect foundations, often unattainable, and requires full knowledge of the ground and the outline and loading of the superstructure; but it can be achieved more often than it actually is. Foundation design is still an art as well as a science. The interpretation of results of soil-mechanics investigations is the responsibility of the engineer.

Brief references are made in the book to volumetric changes of soil due to frost and heat, tree roots and other vegetation, and the swelling of clay soils. It is often found that these cases are difficult to solve successfully. For instance, the position of a chimney stack in relation to a brick kiln is critical if the works are on clay, as is usual; the deflection from the vertical of some chimneys at brickworks is most apparent and is due to this cause. The effects of tree roots is an extensive subject including the laws of the country, which were formulated long before a study of these effects was made.

The damage to structures by expansive clays, such as occur in South Africa, is an interesting study. The phenomena are widespread there and have caused much structural damage to large and small buildings. For instance, bungalows built on the veldt for the new goldmines may

<sup>\* &</sup>quot;Foundation Failures." By C. Széchy.
[London: Concrete Publications Ltd. 1961.
Price 20s. In Canada and U.S.A. 5.0 dollars.]

rise some 4 in. towards their centres on plan; this upheaval, the effect of which on doors, windows and partitions can be imagined, took place slowly during the first three to four years. Preventive measures, the cost of which is high in comparison with the total cost of the structure, may range from the provision of tension piles to special preparation of the site prior to construction.

It is hardly possible to deal in detail with such problems as these in a first edition, particularly when the information is so widely scattered and not readily available. Dr. Széchy has done a fine job in collecting so many different examples all of which are instructive to civil and structural engineers.

MR. DONOVAN H. LEE writes as follows.

There is a wealth of cases of failures described in this book; some are historic, like the Transcona silos in Canada, and a number in Western Europe and Britain, for example the railway cutting at Wembley which slipped in 1918. About half of the cases are from the author's native country, Hungary, and it may surprise some readers to learn how many failures of foundations there are; unfortunately there must be a great number in almost every country, and because of this a book of this type is likely to be valuable in every civil engineer's library.

The technical descriptions are mostly very clear and the related illustrations and graphs or diagrams are in general easily followed; in a few cases, however, they cannot be followed without some patience. The causes of practically all the failures are convincingly explained, and in many cases detailed data of the properties of the soil are given or the defects in the design or execution of the structure, or the temporary works as the case may be, are described.

described.

Students and young engineers may find it of great interest to see the consequences of a retaining wall without weep holes, excessive bearing pressure on cohesive soils, the possible consequences of excavating alongside and below existing loaded foundations and the inadequate bracing of cofferdams, and other defects in execution. The more experienced engineer may find of more interest the failures due to excessively rigid foundations, foundations of different types under the same building, and other but not so

obvious causes such as an example of trouble caused by unnecessary piling.

The publication of this book immediately prior to the Sixth International Congress of Soils Mechanics and Foundation Engineering, which is being held in Paris this month, is timely, though fortuitous.

#### Tay Road Bridge.

THE proposals for a road bridge over the Firth of Tay include a bridge structure 7470 ft. in length costing about £4,000,000. The construction would be of prestressed concrete and would provide two 24-ft. carriageways. The two main navigation spans would each be 240 ft. long. The viaduct on the northern side of the navigation spans would comprise thirty-seven spans of 120 ft. each and four shorter spans, and on the southern side eighteen spans of 120 ft. each and one shorter span. The foundations would comprise piles driven down to rock. The site of the bridge would be east of the existing railway bridge. The clearance under the navigation spans would be about 78 ft. above mean tide level.

The consulting engineer to the Tay Road Bridge Joint Committee is Mr. W. A. Fairhurst.

#### An Honour.

MR. W. A. FAIRHURST, M.I. Struct.E., senior partner in the firm of consulting engineers Messrs. F. A. Macdonald & Partners, has been appointed Commander of the Order of the British Empire. Among the notable works for which he and his firm are responsible is the Queen's Bridge, Perth, which is described in this journal for August 1960 and was opened by Her Majesty the Queen. Mr. Fairhurst is the author of "Arch Design Simplified" and joint-author of "Design and Construction of Reinforced Concrete Bridges."

#### Bulletin Received.

"Repair of Structures and Pavement by Thin Concrete Patching." Bulletin No. 260. Highway Research Board. (1960. Price 0.60 dollars.)—Contains reports on "Latex-modified Mortar in the Restoration of Bridge Structures" by S. M. Cardone, M. G. Brown, and A. A. Hill, and "Bonded Resurfacing and Repairs of Concrete Pavements" by W. G. Westall.



to harness 20,000 million gallons of water for the irrigation of new Australian pastures.
Liseapol N has been specified for use in the construction.
This is the L.C.L. agent which has proved invaluable in obtaining workable concrete mixes of maximum compaction.



### LISSAPOL N

Full information on request

IMPERIAL CHEMICAL INDUSTRIES LIMITED LONDON SW1 ENGLAND

1193

#### CELSIUS

1188

celsius See THERMOMETER (person)

celt 1. n., chisel-edged prehistoric tool (imaginary

celt 2. n., (pl.) peoples speaking or having spoken languages akin to that of the Gauls (Bretons, Cornish. Welsh, Irish. Manx, Gaels) (sing.) member of such people.

celtic (adj.; -ically) of the Cc. (Celtic fringe, the Scots, Irish, Welsh and Cornish, in relation to the U.K.) (n.) the Celtic language, celticism, celtomania, celtomaniac, celtophobe, celtophobia, nn. (L. Celta)

cement 1. n.; Substance made by calcining lime and clay, applied as paste and hardening into stony consistence, and used as material for floors and walls and tanks or as mortar: TUNNEL C. is particularly strong, rapid hardening, weather resistant c. Best C. see The Tunnel Portland Cement Company Limited, 105 Piccadilly, London W.1 GROsvenor 4100.

cement 2. v.t. Apply c. to, line or cover with c., unite (as) with c. To C. for best results see TUNNEL

cemetery n., Burial ground other than churchyard (Gk. Koimao, put to sleep)

cenobite see COENOBITE

cenotaph (-ahf) n. Sepulchral monument to one whose remains are elsewhere.

censer n Incense-burning vessel. Cense v.t. adore or perfume with incense (INCENSE 2)

censor 1. n. Ancient-Roman supervisor of census and public morals: modern official examining plays, books. news. correspondence, etc. to suppress what is immoral or seditious or (esp. in war) inopportune person assuming the right of judging others. 2. v.t Examine or make excisions etc. as in c. Censorial a. (-lly), of

#### Vehicles for Ready-mixed Concrete.

Particulars are given in the following of recent developments in the construction of transit mixers for the supply of readymixed concrete.

#### A Lightweight Mixer.



Fig. 1.

tents are controlled by a flow-meter and check-valve. The mixing-drum unit was developed by the British Aluminium Co., Ltd., and made by Messrs. Melling & Bath, Ltd. The vehicle was designed and built by Messrs. Davies Brothers (Denton) Ltd.

#### A Large Capacity Mixer.

What is claimed to be the transit mixer (Fig. 2) having the largest capacity in this country went into service recently. It is of 9-cu. vd. capacity and is mounted on an eight-wheel chassis incorporating the latest form of hydrostatic drive. To keep the total weight to a minimum, the vehicle is operated by a two-stroke engine and has a glass-fibre driving cab. In order not to exceed the limit of 24 tons for an eightwheel commercial vehicle, as imposed by the Ministry of Transport regulations, the carrying capacity is restricted to 8 cu. yd. Two of these vehicles are in service with Ready Mixed Concrete Ltd., and others are to be added to that company's fleet



Fig. 2.

The drum of a new 4-cu. yd. transit mixer (Fig. 1) exhibited at the Commercial Vehicle Show last year is constructed of aluminium, and thereby the weight is reduced by 12 cwt. from that of similar steel drums which weigh about 3 tons. The power required for agitating the concrete is 5 h.p., for charging 9 h.p., and for discharging 2-4 h.p. The drum rotates at a speed of 7 to 10 r.p.m., 7 to 12 r.p.m., and 10 to 20 r.p.m., respectively during these operations. A 120-gallon tank for the mixing water and a 16-gallon tank for flushing out the drum are situated behind the driver's cabin, and their con-



Fig. 3. (See page 264.)

of about four-hundred vehicles. The mixing unit was manufactured by Messrs. Ransome & Rapier Ltd.

#### Hydraulic-drive Mixer.

A new transit mixer introduced at the Public Works Exhibition last year has a hydraulic drive and the capacities of the drum are 3½, 4 and 6 cu. yd. One control lever only actuates charging, agitating, mixing and discharging operations; hydraulic operation eliminates the use of cables and rods. Two control units are

provided, one being in the driver's cab and the other at the rear of the vehicle. A meter indicates the correct speed for the various operations and also records a running total of the number of revolutinas of the drum between charging and mixing for each journey. The mixer, an illustration of which is given in Fig. 3, is produced by Winget Ltd.

#### FIFTY YEARS AGO.

From "Concrete and Constructional Engineering", July, 1911.

Ornamental Concrete Stairways.



The illustration shows H.M. King George V and Queen Mary descending one of the stairways at the Crystal Palace, London, on the occasion of the Festival of Empire, which was held in the summer of 1911. Since that date there have been three sovereigns, the Empire has been attenuated, and the Crystal Palace has been burnt down, but some of the ornamental concrete stairways are intact. The stairways were designed by Mr. Burnard Geen and constructed by the Empire Stone Co., Ltd. The terrace adjacent to the stairways was the site last month (June 1961) of the International Construction Equipment Exhibition.

#### A Russian Hydro-electric Works.

One of the exhibits at the Russian Trade Fair which is being held in London during the present month is a model of a hydroelectric power station being built at Bratsk in Eastern Siberia. Having a capacity of 4,500,000 kw., the station, which is due to start operating towards the end of this year, will be probably the largest hydro-electric station in the world. The works, which is being constructed at the Padun Gorge on the River Angara, includes a concrete gravity dam 420 ft.

high reduced in weight by hollow deformation joints. The project involved the excavation of 5,000,000 cu. yd. of earth and rock, placing 17,000,000 cu. yd. of earth and rock filling, and placing 7,500,000 cu. yd. of concrete including reinforced concrete.

Six hydro-electric power stations are to be built on the River Angara of which the Bratsk project is the second. A station to be built on the Yenisei is to have a capacity of about 6,000,000 kw.

#### "CONCRETE SERIES"

#### BOOKS ON FOUNDATION ENGINEERING

#### A NEW BOOK Published July 1961

#### DESIGN AND CONSTRUCTION OF FOUNDATIONS

By G. P. MANNING, M.Eng., M.I.C.E.

A dissertation, with much practical data, on the design of most types of foundations, including notes on constructional operations and materials. Many examples drawn from the Author's extensive experience. 226 pages. Numerous diagrams, working drawings, design charts etc.

Price 24s.; by post 25s.

In Canada and U.S.A. 6 dollars.

#### A NEW BOOK

Published March 1961

#### FOUNDATION FAILURES

By C. SZECHY (Professor of Foundation Engineering, Budapest)

The author examines the causes of the failure, due to defective foundations, of numerous structures throughout the world. A useful guide to the avoidance of trouble.

115 pages. Price 20s.; by post 21s. 123 diagrams and photographs. In Canada and U.S.A. 5 dollars.

Second Edition. Published 1960

#### REINFORCED CONCRETE PILING AND PILED STRUCTURES

By F. E. WENTWORTH-SHEILDS, W. S. GRAY, B.A., and H. W. EVANS,

Describes the design manufacture, and driving, of precast concrete piles. Design of piled structures with examples and illustrations. Design data in accordance with the latest British Codes of Practice. 149 pages, 116 illustrations, 17 tables.

Price 18s.; by post 19s.

In Canada and U.S.A., 4 dollars.

Revised Edition 1957

#### RAFT FOUNDATIONS.—THE SOIL-LINE METHOD

By A. L. L. BAKER, D.SC. (TECH.), A.M.INST.C.E.

Describes in detail with worked examples, the Soil-Line Method, a practical and economical way of taking into account variation of earth pressure.

148 pages, 89 illustrations.

Price 12s.; by post 13s. In Canada and U.S.A., 2-80 dollars.

To be Published Shortly

#### AN INTRODUCTION TO DEEP FOUNDATIONS AND SHEET-PILING

By DONOVAN H. LEE, M.I.C.E., F.ASCE., M.I.Mech.E.

This book is the successor to the author's "Sheet Piling, Cofferdams and Caissons ". It is much enlarged and now deals with soil investigation, bearing piles, and sub-aqueous tunnels, as well as making and driving sheet-piles, the design of sheet-pile walls, and the design and construction of cofferdams, cylinders and open and pneumatic caissons. A feature is the numerous examples of actual works throughout the world.

260 pages. Price 20s.; by post 21s. 2d. Numerous diagrams and photographs, In Canada and U.S.A. 5 dollars.

For complete particulars of these and other books in the "CONCRETE SERIES"

dealing with all aspects of design and construction in reinforced and prestressed concrete write to

> CONCRETE PUBLICATIONS LTD... 14 DARTMOUTH STREET, LONDON S.W.1

#### DATA FOR PRICING REINFORCED CONCRETE.

MATERIALS (Delivered London).

AGGREGATES (per cu. yd.).

Washed sand: 26s. 9d. Graded gravel (1 in.): 24s. 3d. Pit ballast: 25s. 6d.

CEMENT (per ton).

Ordinary Portland.—6 tons and upwards: 115s. 3d.; 1 ton to 6 tons: 127s. Rapid-hardening Portland: As ordinary Portland plus 10s. 6d. "Aquacreta and "417": As ordinary Portland plus 32s. 6d. "Colorcrete" (buff. 10) and khaki): As ordinary Portland plus 60s. "Snowcrete" (white): 280s. 9d. "Super-Cement": As ordinary Portland plus 32s. 6d.

High-alumina cement.-6 tons: 314s. 6d.

"Super Snowcem" waterproof cement paint: 100s. per cwt.

REINFORCEMENT (per ton ex stock including delivery in quantities from 10 to 500 ton Plain mild steel rods per B.S. No. 785 .- 1 in. and over: £50 5s.; ‡ in. and ‡ in : £51; \$ in.: £51 15s.; \$ in.: £53 7s. 6d.; \$ in.: £54 17s. 6d.; \$ in.: £58 17s. . .

Hot-rolled deformed bars: As plain bars plus £1.

High-tensile (minimum yield point 44,000 lb. per sq. in.): As mild steel plus .9s. (For basic prices and allowances for quantities exceeding 500 tons and extras for quantities less than 10 tons, lengths greater than 40 ft. or less than 5 ft., bundling, labelling, and delivery in other areas, see "Concrete Year Book, 1961".) Fabric per B.S. 1221A (per sq. yd.).—No. 109: 3s. \(\frac{1}{4}\).; No. 121: 5s. 7\(\frac{1}{4}\).; No. 124:

38. 4\d.; No. 125: 28. 10d.; No. 126: 28. 6\d.

Timber.—Sawn deal shutter boards: £95 to £100 per standard (165 cu. ft.); remboards: 1s. (av.) per sq. ft.; 1\frac{1}{2}-in. boards: 1s. 3\frac{1}{2}d. (av.) per sq. ft.

#### MATERIALS AND LABOUR.

Based on net cost of materials plus 10 per cent. and net cost of labour plus 45 per cent. for insurances, etc. (10 per cent.), on-costs (22 per cent.) and profit (10 per cent.) on gross cost = 13 per cent. on net cost). No allowance for non-productive ordinary time. overtime, travelling time, fares, subsistence, etc. Wages (per hour).—Carpenters a joiners: 5s. 14d.; labourers: 4s. 6d.; mixer and hoist operators: 5s.; bar benders: 4s. 11d. PORTLAND CEMENT CONCRETE (1:2:4).

Foundations (per cu. ft.).—3s. 6d.

Suspended slabs (per sq. yd.).—6 in., 18s. 3d.; 7 in., 21s. 4d.; 9 in., 27s. 3d.

Beams (per cu. ft.).—4s. 1d. Columns (per cu. ft.).—4s. 7d.

Walls (per sq. yd.).—6 in., 19s. 11d.; 9 in., 29s. 10d.; 12 in. and over (per cu. ft.), 3s. 7d.

Extra (per cu. yd.) for rapid-hardening Portland cement. 1:2:4.-2s. 8d.

REINFORCEMENT.-Mild steel rods cut, bent and fixed (per cwt.).

	In floor slabs and beams.	In columns.	In walls.	Stirrups, binders, etc.
1 in. and over	758. 6d.	81s. 2d.	78s. 10d.	_
in. and in.	76s. 3d.	81s. 11d.	79s. 7d.	
in.	778. 1d.	82s. 9d.	80s. 5d.	-
in.	84s. 7d.	91s. 5d.	89s. 2d.	
in.	86s. 3d.	93s. 1d.	90s. 10d.	103s. 4d.
A in.	88s. 6d.	95s. 3d.	93s. od.	105s. 6d.
in.	89s. 7d.	96s. 4d.	945. 1d.	106s. 7d.

Fabric per B.S. No. 1221A in flat areas (per sq. yd.) including straight cutting .-No. 109: 4s. 5d.; No. 121: 8s.; No. 124: 4s. 9\d.; No. 125: 4s. 2\d.; No. 126: 3s. 7\d.

SHUTTERING (FORMWORK).—Assuming five uses of wooden shutters for floor soffits and walls, and three uses for beams.

Soffits of floors, flat roofs, etc. (per sq. yd.): 16s. 3d.; ditto sloping: 18s. 1d. Walls and partitions (per sq. yd.): 19s. 11d.; ditto curved: 26s. 10d. Rectangular beams, lintels, columns, etc. (per sq. ft.): 2s. 8d.; ditto circular: 3s. 8d.

This page is prepared specially for "Concrete and Constructional Engineering" and is strictly copyright.

#### MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 3d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 13s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.

Advertisements for the August number must reach this office, 14 Dartmouth Street, London, S.W.1, by July 11.

#### SITUATIONS VACANT.

SITUATIONS VACANT. Concrete laboratory technicians with good experience are required for our central laboratories in London. Apply, with full details, to Massas. Samparao, 40 Grosvesor Gardens, London, S.W.I. Starting salaries up to £750 per annum.

SITUATIONS VACANT. Consulting engineers require senior and assistant engineers experienced in design, detaining and construction of reinforced concrete structures. Excellent opportunities in expanding practice with first-class conditions of employment, pension, etc. Apply in writing, with full details, to Jonn Busca & Associates, 28 St. George's Road, London, S.W.19.

SITUATION VACANT. Qualified engineer-designer required, experienced in reinforced concrete, preparing schemes, visiting sites, etc. Must have degree and/or professional qualifications. Good salary, and superannuation scheme after probationary period. Applications, stating age, education, qualifications and experience, to A. Mont & Co. Lr.D., 2 Exchange Place, Middleibrough.

SITUATIONS VACANT. Harrow reinforced concrete engineers and contractors require experienced detailing-draughtsmam. Five-days week; interesting work; modern offices; pension scheme after qualifying period. Write Biranauma, 167-173 Imperial Drive, Harrow, or telephone for appointment Field End 770s.

SITUATIONS VACANT. Reinforced Concrete Designers, Detailers and Draughtsmen required at Glasgow, Newhouse, Edinburgh, Gateshead, Manchester and Altrincham. Progressive positions with established company. Fivedays' week. Non-contributory pension scheme and profit-sharing bonus. Apply to the Divisional Engineer at any of the Branch Offices or to the Regional Engineer, The SQUARE GRIP REINFORCEMENT CO., LTD., Market Street, Altrincham, Cheshire.

SITUATIONS VACANT. CLARKE, NICHOLLS & MARCEL require experienced reinforced concrete designer-detailers and draughtsmen for their Bristol and Cardiff offices. Positions are pensionable, and offer first-class experience for those studying for professional qualifications. A senior structural engineer is also required for the Cardiff office, and preference would be given to an A.M.I.Struct.E. Apply to 10 Appley Road, Bristol 8, or South Wales Institute of Engineers Building, Park Place, Cardiff.

SITUATIONS VACANT. Reinforced concrete and structural steelwork designers and detailers required at Bristol head office and in the London office. Permanent positions covering most fields of reinforced concrete and steelwork design. Pension and insurance schemes. Attractive salaries. Full details to Norkis Couscurants Ltd., Beacon House, Queen's Road, Chiton, Bristol, S.

SITUATIONS VACANT. Consulting engineers have vacancies for the following: Reinforced concrete designers with A.M.I.Struct.E.; Designer-detailers with H.N.C. or similar; Detailers with minimum two years' experience. The positions are permanent, with opportunity for advancement. Modern office and pleasant conditions. Salaries in accordance with experience. Apply BYLANDER, WADDELL & PARYMERS, 160 Wembley Park Drive, Wembley, or 10 Carver Street, Sheffield.

SITUATIONS VACANT. A few experienced reinforced concrete designer-detailers required for interesting and progressive posts with consulting engineers at their offices in Cannon Street, London, E.C.4. Salary range (\$55-4500. Luncheon vouchers. Pension scheme. Apply Ecwang A. Pitchers & Partiers, \$58-60 Cannon Street, Lemion, E.C.4. Telephome: City 2292.

SITUATION VACANT. Resident engineer urgently required for reinforced concrete work on large multi-storey housing project in Loadon. Previous site experience, A.M.I.C.E. or A.M.I.Struct.E. essential. Apply CLARES, NICHOLLS & Mascal, a? Westbourne Grove, London, W.z. Telephone: Bayswater 86E.

Telephone: Bayswater 8981.
SITUATIONS VACANT. Detailers experienced in reinforced concrete required for London professional office.
The work in varied, comprising all types of construction in
concrete and steel, and offers scope for anyone interested
in gaining design experience. Permanent position with
excellent prospectis. Five-days' week. Apply, stating full
experience, to Farmer & Dark, Romney House, Tufton
Street, London, S.W.T.

SITUATIONS VACANT. Reinforced concrete engineers require experienced section-leaders and detail/draughtemen. Interesting work, five-days' week, luncheon vouchers, own pension scheme, etc. Salaries in accordance with experience. Apply in writing to Tur. REINFORCED CONCRETE STEES. Co. LTD., 54 Victoria Street, Westminster, S.W. r.

S.W.I.

S.W.I.

SITUATIONS VACANT. Reinforced concrete designesdetailers and detailers required by LEGRARD & GRART in
their South London and Edinburgh offices. Applicants
should have three years' minimum experience in position
applied for. Good salaries and prospects, luncheon
vouchers, etc. Interview by appointment. Telephone:
London, MACaulay 6497; Edinburgh, CAL 3807.
SITUATION VACANT. Representative. Opportunity for
enthusiastic young man to obtain position on sales technical
stell of company with represented reproduct indiagnoscable to

SITUATION VACANT. Representative. Opportunity for enthusiastic young man to obtain position on sales technical staff of company with renowned product indispensable to reinforced concrete construction. Initially mobile over 50-miles ratios of South Coast—London. Knowledge of reinforced concrete, and holding a driving licence advantageous. Applicants must be of pleasant personality, keen, energetic, conscientious, adaptable, and should have been educated to the standard of G.C.E. Written applications, treated in strict considence, with full particulars, details of qualifications, etc., be Box 4794, Concerts And Constructional Engiseries, 14 Dartmouth Street, London, S.W.I.

# Join the BRC

team of

#### **EXPERIENCED**

REINFORCED

# CONCRETE DESIGNER/DETAILERS and DRAUGHTSMEN

#### at any of the Design Offices at

STAFFORD LONDON BIRMINGHAM BRISTOL CHELMSFORD

LEEDS
LIVERPOOL
M MANCHESTER
NEWCASTLE
RD GLASGOW
DUBLIN

Apply

Chief Engineer:
A. P. Mason, B.Sc., M.I.C.E., M.I. Struct. E., M.ASCE
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD

SITUATION VACANT. Section leader to supervise section designing reinforced concrete structures. University graduate (British) preferred, conversant with London Buildings Bye-laws and accustomed to discussions with architects. Frequent visits to sites. Salary subject to discussion. Write CHEFF ESCHERER, TROLLOPE & COLLS LTD., I Noble Street, Gresham Street, London, E.C.2.

LTD., 7 Noble Street, Greshum Street, London, E.C.2.

SITUATION VACANT. Major mining concern in West Africa wishes to employ a Clerk of Works, to be in charge of all building and construction work on the property. Experience in reinforced concrete work on the surface and underground is essential. The Clerk of Works will also be responsible for the Sawmill and Carpenter's Shop. The starting salary will be not less than £140 per month and accommodation and passages are provided free for the applicant and his wife. Tours are of 23 months followed by 3 monthly lisave. The appointment is permanent and pensionable. The climate is healthy and suitable for children. Write, with full particulars and qualifications, experience and age, to Box 4764, Concert, App Constituctional Engineering, 14 Dartmouth Street, London, S.W.z.

S.W.L.

SITUATIONS VACANT. Designer-detailers with minimum of three years' experience in reinforced concrete required in our London and Guildford offices. Salary according to qualifications and experience. Persion scheme. Write or telephone for appointment, either Balham 2456 or Guildford 2453. TREECON INDUSTRIAL DRESSE RECHERGE, ILE STATION PARAGE, Balham High Road, London, S.W.12.

Road, London, S.W.12.

SITUATION VACANT. Representative with proved ability and connections, particularly with architects and municipal authorities, etc., required by prominent designers, suppliers and sub-contractors to the building and civil esquineering industries for north-east, east and eath-cant London and adjoining House Counties. Superannuated staff appointment with salary, commission, expenses and car provided. Write, giving full details of experience, calary sequired, age, etc., to The Secretary, The Rose River Co. Ltd., 100 Stewarts Road, London, S.W.5.

#### QUALIFIED OR POST-GRADUATE ENGINEERS

required to work on the design of Precast Concrete Frame Structures, including Multi-Storey Flats.

Salaries range from £850 to £1,150 per annum, according to age and experience. Prospects of promotion, permanent position, Staff Pension Fund and Profit-sharing Scheme, five-days' week.

Apply: Concrete (Northern) Ltd. Stourton, Leeds, 10,

# STRUCTURAL ENGINEER EXCEPTIONAL OPPORTUNITY

Consulting Civil Engineers, Westminster, respire a fully qualified structural engineer with wide experience for position as chief designer in reinforced and prestressed concrete and structural steelwork, including bridges and buildings.

Prospects of partnership interest in firm.

Write in confidence, stating age and full details of experience and qualifications, to Box 4765, CONCRETE AND CONSTRUCTIONAL EMGINEERING, 14 Dartmouth Street, London, S.W.J.

#### E. J. COOK & CO. (ENGINEERS) LTD.

invite applications from reinforced concrete esigners who are at present earning £1100-£1400 pc. annum and are prepared to accept responsibility. Write or telephone for application form from 54 South Side, Clapham Common, London, S.W.4. (MACaulay 5528.)

SITUATION VACANT. Deputy to chief engineer required for leading structural consultants, London bead office. Commencing salary £,0,000 per annum rising by annual increments of £,000 per annum not £,000 per annum and subject to merit thereafter. Applicants must be chartered structural engineers and of exceptional technical and administrative ability, between the age of 35 and 45 with at least § years' experience in position of full personal responsibility for the preparation of calculations, projects and detailed designs for large reinforced concrete v. 2. Pension scheme available. Applications, which wis betreated in the strictest confidence, to Box 4790, Concerned AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Designer of shuttering and builders' plant required by manufacturer. Concrete mould experience advantageous. Full details of experience and qualifications to CHIEF ENGINEER, A.B. MOULD & CONSTRUCTION CO., LTD., Vulcan Works, New Addington, Croydon.

# Experienced Reinforced Concrete

#### DESIGNERS & DETAILERS

with minimum H.N.C. are required by a leading firm of Consulting Engineers for their LONDON and EPSOM, SURREY, offices. These are permanent positions with a five-days' week, luncheon vouchers and pension scheme. Please write fully to the Personnel Manager.

> W. S. ATKINS & PARTNERS 158 Victoria Street London, S.W.1

#### C. J. PELL & PARTNERS CONSULTING ENGINEERS

Invite applications from Reinforced Concrete Designers, Designer-Detailers, Detailers and Draughtsmen, for appointments at Head Office and New Offices being opened in Croydon Area. A number of interesting projects are in various stages of design, in Reinforced, Precast and Prestressed Concrete construction, Structural Steelwork and Laminated Timber.

Appointments are permanent, and every encourage-

Applications to be permanent, and every canoning ment is given for advancement. Five-days' week, Luncheon Vouchers, Bonus, Holiday arrangements honoured. Applications to 4 Manchester Square, London, W. s. Welbeck 8188.

#### **FELIX J. SAMUELY & PARTNERS**

Consulting Structural Engineers 231/233 Gower Street, London, N.W.s

invite applications from

#### **Qualified Engineers**

to supervise and administer interesting projects to supervise and nominister interesting projects involving skin structures, precises and pre-stressed concrete, steel and timber construction. Men who appreciate the problems associated with modern building, especially those which affect the architect and related consultants, will have good prospects.

#### Designer-Detailers

preferably H.N.C. standard, for reinforced pre cast and prestressed concrete, timber and steelstructures.

Five-days' week. s' week. Luncheon vouchers. Pension Holiday arrangements honoured. Please apply in writing, giving details of experience, and salary required



#### CIVIL ENGINEERING DRAUGHTSMAN

A Civil Engineering Design Draughtsman is required for a wide variety of work associated with manufacturing plants in the United Kingdom. Broad experience of this kind of work together with a knowledge of building details is essential.

The post will be located in the head office of the Company. A good starting salary will be past with regular reviews. Preferred age 25-35 with a minimum of O.N.C.

Please write in confidence to

THE CHIEF DRAUGHTSMAN. MINNESOTA MINING & MANUFACTURING COMPANY LTD. 3M HOUSE, WIGMORE STREET, LONDON, W.I.

#### SALES MANAGER

required

for Steel Reinforcement Specialists

Applicants must be experienced in this field of work, having own connections with building contractors, curveyors, etc. Salary £1,250 to £5,200 depending on experience and ability. Excellent opportunity for advancement. Details of experience, etc., to BOX 4759, CONCRETE AND CONSTRUCTIONAL EMBLIERRING, 24 DARTHOUGH STREET, LONDON, SW.I.

SITUATION VACANT. Structural engineer required for SITUATION VACANT. Structural engineer required for design of modern conscrete structures. Applicants should have University Degree or equivalent, and four years' experience in design. Apply, stating experience, etc., and salary required, to R. GHLEN, B.S.C., A.M.I.C.E., Consulting Engineer, 40 Victoria Square, Belfast.

SITUATIONS VACANT. Reinforced concrete designers and detailers very urgently required, Bristol/Bath. Excellent terms and conditions. Telephone: KEYNSHAM 3621.

#### CONSULTING ENGINEERS

have vacancies in their modern offices in Hammersmith for:

#### SENIOR ASSISTANT ENGINEERS

professionally qualified with minimum seven years' experience in reinforced concrete. Salary £1,000-£1,300 plus BONUS

JUNIOR ENGINEERS, DETAILERS AND DRAUGHTSMEN

with drawing office experience in reinforced concrete and ambition to take on more responsibility.

> Salary (800-ft,000 plus BONUS according to age, qualifications and experience.

All vacancies are permanent, pensionable and salaries are reviewed annually. Bonus is generous and based on the individual's effort. Five-days' week. Luncheon Vouchern. Car allowances and travelling expenses between home and office are also paid.

Please write or telephone to: CHARLES WEISS AND PARTNERS, 123 KING STREET, HAMMERSMITH, LONDON, W.6 RIVERSIDE 7843

#### **OUALIFIED ENGINEER**

required

to take charge of a

REINFORCED CONCRETE CONTRACTORS'
DESIGN OFFI 'E

Profit sharing and Pension Scheme

F. BRADFORD & CO. LTD., ANGEL ROAD, EDMONTON, LOHDON, N. 18

Telephone: Евмонтон 4267

# EXPERIENCED BEINFORCED CONCRETE ENGINEERS, DESIGNERS AND DETAILERS REQUIRED

Numerous companies on our registers have vacancies for experienced men in these categories. We are specialists in such technical appointments. NO FEES.

BUSINESS VACANCIES BUREAU LTD., 32 Victoria Street, London, S.W.1. Telephone: ABBey 7200

#### SERVICES OFFERED.


SERVICES OFFERED. Qualified engineer and experienced team offer to the profession rapid and accurate design-detailing services. Box 4767, Concerte AND Constructional Engineering, 14 Dartmouth Street, London, S.W.1.

#### FOR SALE.

HIGH-QUALITY FORKLIFT TRUCKS I E PETROL, DIESEL AND ELECTRIC MODELS

By Coventry Climax, Conveyancer, Wingrove & Rogers, Lansing Bagnall, etc. From £450-£1500.
Full details on application. SPRED ELECTRICS Dept. CCE., Church Street, Basiord, Nottingham. Tel. 75716.

FOR SALE. Steel guttering, ironwork, sheet metal work. E. STEPHENS & SON, LTD., Bath Street, London, E.C., Clerkenwell 1731.



For compacting mortar cubes for compression tests to

B.S. 12/1958, 146, 1370, 915 Automatic Time Control

"CAPCO"

# H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes: Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical Moulds; Compacting Factor Apparatus—Standard and Automatic; Sieve Vibrators and Sieves; etc.

## CAPLIN ENGINEERING CO. LTD

(ESTABLISHED 1918)

POLLEN HOUSE, 19/12 CORK STREET, LONDON, W.I Phone: REGENT 0716. Grams: CAPLINKO, LONDON. Telex: 23255. Cables: CAPLINKO, LONDON. Works: IPSW

#### "CONCRETE SERIES"

# **BOOKS ON CONCRETE**

For a complete catalogue giving prices in sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS LIMITED
14 DARTMOUTH STREET, LONDON, S.W.I



General Visco of Plant at Richmansscorth.

#### OF OUR MODERN AGGREGATES PLANTS CONCRETE

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16' up to 2', either crushed or natural.

Special Specifications made to order.



STONE COURT BALLAST CO. LTD. PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.I

Telephone: Tata Gallery 3456.



# EXPERIENCED REINFORCED CONCRETE ENGINEERS, DESIGNERS AND DETAILERS REQUIRED

Numerous companies on our registers have vacancies for experienced men in these categories. We are specialists in such technical appointments. NO FEES.

BUSINESS VACANCIES BUREAU LTD., 32 Victoria Street, London, S.W.1. Telephone: ABBey 7200

#### SERVICES OFFERED.


SERVICES OFFERED. Qualified engineer and experienced team offer to the profession rapid and accurate design-detailing services. Box 4767, Concentra and Constructional Engineering, 14 Dartmouth Street, London, S.W.I.

#### FOR SALE.

HIGH-QUALITY FORKLIFT TRUCKS
PETROL, DIESEL AND ELECTION
MODELS

By Coventry Climax, Conveyancer, Wings & Rogers, Lansing Bagnall, etc. From £450-£182. Full details on application. SPRED ELECTRIS Dept. CCE., Church Street, Basford, Nottingham Fel. 75716.

FOR SALE. Steel guttering, ironwork, sheet metal work. E. STEPHERS & SON, LYD., Bath Street, London, E.C., Clerkenwell 1731.



For compacting mortar of for compression tests to

B.S. 12/1958, 146, 1370, 915 Automatic Time Control

"CAPCO"

# H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes: Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical Moulds; Compacting Factor Apparatus—Standard and Automatic; Sieve Vibrators and Sieves; etc.

## CAPLIN ENGINEERING CO. LT!

(ESTABLISHED 1918)

POLLEN HOUSE, 10/12 CORK STREET, LONDON, W.I Phone: REGENT 0716. Grams: CAPLINKO, LONDON. Telex: 23255. Cables: CAPLINKO, LONDON, Works: IPSW

"CONCRETE SERIES"

# **BOOKS ON CONCRETE**

For a complete catalogue giving prices in sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS LIMITED
14 DARTMOUTH STREET, LONDON, S.W.I



General View of Plant at Richmansworth.

#### ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.

Special Specifications made to order.




STONE COURT BALLAST CO. LTD.

PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.I

Telephone: Tate Gallery 3456.





Specialists in Reinforced Concrete Design and Suppliers of Reinforcement

#### THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

London, Birmingham, Bristol, Chelmsford, Leeds, Leicester, Liverpool, Monchester, Newcastle, Cordiff,
Glasgow, Dublin, Belfast, Bulawayo, Calcutta, Johannesburg, Singapore, Vancouver
Export Sales: 54 Grosvenor Street, London W.I

M-W.18/8

